

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location Edged Chicago ORD01, IL -- station KDPA, America/Chicago
Building OSM 1481581948
Edged Chicago ORD01
Facade gap not applicable -- one building, no second facade
Weather record 43,457 real hourly records from KDPA
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs.

Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-05-01 (crossing)
Plant limit 21.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 12 of 24 hours with 2 mode changes. The reactive incumbent took 14 hours -- 2 more -- but declared 2 unsafe hours against the agent's 0.

Agent 12 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)

Incumbent 14 of 24 hours free cooling, 2 mode change(s), 2 unsafe hour(s)

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	4.715	21.0	4.440	1.002
01	FREE	yes	-	5.000	21.0	5.000	0.915
02	FREE	yes	-	4.165	21.0	3.330	0.842
03	FREE	yes	-	5.555	21.0	6.110	0.768
04	FREE	yes	-	6.390	21.0	7.220	0.717
05	FREE	yes	-	6.110	21.0	7.780	0.906
06	FREE	yes	-	8.080	21.0	8.330	0.892
07	FREE	yes	-	10.835	21.0	10.000	1.540
08	FREE	yes	-	13.610	21.0	12.220	2.078
09	FREE	yes	-	15.835	21.0	15.000	2.111
10	FREE	yes	-	17.225	21.0	16.670	1.831
11	FREE	yes	-	18.860	21.0	18.890	1.545
12	mechanical	no	dry-bulb	21.110	21.0	22.220	1.111
13	mechanical	no	dry-bulb	22.780	21.0	25.000	0.935
14	mechanical	no	dry-bulb	24.720	21.0	27.220	1.042
15	mechanical	no	dry-bulb	26.390	21.0	28.330	0.891
16	mechanical	no	dry-bulb	27.775	21.0	28.890	1.071
17	mechanical	no	dry-bulb	28.055	21.0	28.330	0.974
18	mechanical	no	dry-bulb	27.775	21.0	27.220	1.107

19	mechanical	no	dry-bulb	27.500	21.0	26.110	1.379
20	mechanical	no	dry-bulb	26.110	21.0	23.890	1.457
21	mechanical	no	dry-bulb	25.000	21.0	22.780	1.301
22	mechanical	no	dry-bulb	23.890	21.0	21.670	1.051
23	mechanical	no	dry-bulb	22.500	21.0	20.560	1.125

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 4.715 C, which is 16.285 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.002 C, and the margin is measured, not chosen: 1.002 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 5.000 C, which is 16.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.915 C, and the margin is measured, not chosen: 0.915 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 4.165 C, which is 16.835 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.842 C, and the margin is measured, not chosen: 0.842 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 5.555 C, which is 15.445 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.768 C, and the margin is measured, not chosen: 0.768 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.390 C, which is 14.610 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.717 C, and the margin is measured, not chosen: 0.717 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.110 C, which is 14.890 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.906 C, and the margin is measured, not chosen: 0.906 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.080 C, which is 12.920 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.892 C, and the margin is measured, not chosen: 0.892 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.835 C, which is 10.165 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.540 C, and the margin is measured, not chosen: 1.540 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.610 C, which is 7.390 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 2.078 C, and the margin is measured, not chosen: 2.078 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

09:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.835 C, which is 5.165 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 2.111 C, and the margin is measured, not chosen: 2.111 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

10:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.225 C, which is 3.775 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.831 C, and the margin is measured, not chosen: 1.831 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

11:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 18.860 C, which is 2.140 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.545 C, and the margin is measured, not chosen: 1.545 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.110 C against a 21.0 C limit, so it fails by 0.110 C. It would take a limit 0.110 C higher, or a bound 0.110 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.780 C against a 21.0 C limit, so it fails by 1.780 C. It would take a limit 1.780 C higher, or a bound 1.780 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.720 C against a 21.0 C limit, so it fails by 3.720 C. It would take a limit 3.720 C higher, or a bound 3.720 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.390 C against a 21.0 C limit, so it fails by 5.390 C. It would take a limit 5.390 C higher, or a bound 5.390 C tighter, to change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.775 C against a 21.0 C limit, so it fails by 6.775 C. It would take a limit 6.775 C higher, or a bound 6.775 C tighter, to change this hour.

17:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 28.055 C against a 21.0 C limit, so it fails by 7.055 C. It would take a limit 7.055 C higher, or a bound 7.055 C tighter, to change this hour.

18:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.775 C against a 21.0 C limit, so it fails by 6.775 C. It would take a limit 6.775 C higher, or a bound 6.775 C tighter, to change this hour.

19:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.500 C against a 21.0 C limit, so it fails by 6.500 C. It would take a limit 6.500 C higher, or a bound 6.500 C tighter, to change this hour.

20:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.110 C against a 21.0 C limit, so it fails by 5.110 C. It would take a limit 5.110 C higher, or a bound 5.110 C tighter, to change this hour.

21:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 25.000 C against a 21.0 C limit, so it fails by 4.000 C. It would take a limit 4.000 C higher, or a bound 4.000 C tighter, to change this hour.

22:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.890 C against a 21.0 C limit, so it fails by 2.890 C. It would take a limit 2.890 C higher, or a bound 2.890 C tighter, to change this hour.

23:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.500 C against a 21.0 C limit, so it fails by 1.500 C. It would take a limit 1.500 C higher, or a bound 1.500 C tighter, to change this hour.

WHAT IT IS WORTH OVER FIVE REAL YEARS, AT THIS SITE

Held-out days simulated	912 -- the agent never calibrates on a day it is scored on
Free cooling delivered	16.55 h/day, i.e. 6,045 h/yr
Chiller-hours avoided	+289.2 h/yr against a tuned reactive incumbent

12-hour plan stability 93.9 % of 21,731 re-plans change nothing at all

The ladder, one constraint at a time:

N-56-like: notice 0, skill 1.00, no constraint	+38.8 h/yr
+ switch budget 2, min dwell 3 h	+60.5 h/yr
+ dew-point gate 15 C (Green Grid WP#46 p.6)	+112.9 h/yr
+ notice 3 h, skill 0.50 (no perfect forecast)	+289.2 h/yr
+ unanchored, 4 measured FG offsets rotated	-191.0 h/yr

PRICED, IN THIS STATE'S OWN ELECTRICITY TARIFF

Chiller power	156.1 kW per MW of IT load (0.549 kW/ton, the ASHRAE 90.1-2019 minimum)
Electricity	11.81 cents/kWh (Illinois commercial, 2024 annual)
Energy avoided	45,139 kWh per MW of IT load per year
Value	\$5,331 per MW of IT load per year

Everything above is PER MEGAWATT OF IT LOAD. This project has never measured a data centre's size and will not invent one; a reader who knows their own IT load multiplies once.

WHAT IS NOT CLAIMED

- The chiller COMPRESSOR only. Fans, chilled-water pumps, condenser pumps and cooling-tower fans keep running, and an airside economizer moves MORE air, so fan power can rise. The unmeasured term has the OPPOSITE SIGN, so this is an upper bound.
- Code-minimum chiller efficiency is the OPTIMISTIC end: Standard 90.1 is a floor, hyperscale plants beat it, and a better chiller saves less per hour switched off.
- Full-load kW/ton OVERSTATES the draw at the moment free cooling is available, because free cooling happens when it is cool and a chiller at a cool condenser runs below its rating. IPLV is the lower published number but is an annual-weighted metric under AHRI's assumed load profile, not the part-load point free-cooling weather sits at.
- The heat rejected is APPROXIMATED by the IT load. UPS, PDU and lighting losses inside the envelope add to it; some overhead sits outside the cooled space, so scaling by full PUE would overshoot. No PUE multiplier is applied.
- EIA STATE-SECTOR AVERAGES, not the site's tariff. A Loudoun County campus buys on a large-general-service contract that is not public.
- No carbon, no water, no maintenance and no demand charges. Tower water use moves the OTHER way when the chiller runs less.
- Every caveat on the hours is inherited: the headline is conditional on the bank sitting on the long facade (the refusal guard is priced at -3,124 h/yr where it fires) and the unanchored row is NEGATIVE. Those rows appear here with their signs intact.

HOW TO REPRODUCE EVERY NUMBER IN THIS REPORT

```
cd INTAKE-ARBITER/src && python run_all.py
```

That rebuilds every artefact from saved data and then audits it: 39 checks, 68 published figures re-read out of the files the code itself wrote, and it exits non-zero on any failure. It makes ZERO API calls -- every input is a saved FortyGuard response, a committed geometry file, or the station's own hourly record.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.