

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location Meta Sarpy Data center, NE -- station KMLE, America/Chicago
Building OSM 1253282100
Meta Sarpy Data center
Facade gap not applicable -- one building, no second facade
Weather record 43,165 real hourly records from KMLE
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs.

Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-03-30 (clear_cool)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 10 of 21 hours with 2 mode changes. 8 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 10 of 21 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 10 of 21 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
8 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	13.110	18.0	14.000	4.423
01	FREE	yes	-	13.280	18.0	13.330	3.860
02	FREE	yes	-	13.670	18.0	11.220	3.487
03	FREE	yes	-	13.830	18.0	8.780	3.059
04	FREE	yes	-	14.000	18.0	8.000	2.867
05	FREE	yes	-	14.110	18.0	7.220	2.683
06	FREE	yes	-	14.500	18.0	5.890	2.596
07	FREE	yes	-	15.110	18.0	5.280	2.809
08	FREE	yes	-	15.440	18.0	6.220	3.334
09	FREE	yes	-	16.110	18.0	7.220	4.439
11	mechanical	no	dry-bulb	20.280	18.0	9.000	5.909
12	mechanical	no	dry-bulb	21.110	18.0	9.440	6.355
13	mechanical	no	dry-bulb	20.060	18.0	10.560	6.433
15	mechanical	yes	switch budget	15.280	18.0	10.110	4.479
16	mechanical	yes	switch budget	13.890	18.0	10.720	3.842
17	mechanical	yes	switch budget	12.610	18.0	9.890	3.458
18	mechanical	yes	switch budget	12.110	18.0	9.220	3.246

19	mechanical	yes	switch budget	10.440	18.0	8.110	3.153
20	mechanical	yes	switch budget	10.000	18.0	7.500	3.397
21	mechanical	yes	switch budget	9.000	18.0	5.890	4.080
23	mechanical	yes	switch budget	9.610	18.0	2.390	4.600

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.110 C, which is 4.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.423 C, and the margin is measured, not chosen: 4.423 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.280 C, which is 4.720 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.860 C, and the margin is measured, not chosen: 3.860 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.670 C, which is 4.330 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.487 C, and the margin is measured, not chosen: 3.487 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.830 C, which is 4.170 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.059 C, and the margin is measured, not chosen: 3.059 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.000 C, which is 4.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.867 C, and the margin is measured, not chosen: 2.867 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.110 C, which is 3.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.683 C, and the margin is measured, not chosen: 2.683 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.500 C, which is 3.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.596 C, and the margin is measured, not chosen: 2.596 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.110 C, which is 2.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.809 C, and the margin is measured, not chosen: 2.809 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.440 C, which is 2.560 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.334 C, and the margin is measured, not chosen: 3.334 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is

actually off by.

09:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.110 C, which is 1.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.439 C, and the margin is measured, not chosen: 4.439 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.280 C against a 18.0 C limit, so it fails by 2.280 C. It would take a limit 2.280 C higher, or a bound 2.280 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.110 C against a 18.0 C limit, so it fails by 3.110 C. It would take a limit 3.110 C higher, or a bound 3.110 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.060 C against a 18.0 C limit, so it fails by 2.060 C. It would take a limit 2.060 C higher, or a bound 2.060 C tighter, to change this hour.

15:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.280 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

16:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.890 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

17:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.610 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

18:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

19:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.440 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

20:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

21:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 9.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

23:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 9.610 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan

to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

WHAT IT IS WORTH OVER FIVE REAL YEARS, AT THIS SITE

```
Held-out days simulated    909 -- the agent never calibrates on a day it is scored on
Free cooling delivered      15.78 h/day, i.e. 5,765 h/yr
Chiller-hours avoided     +279.2 h/yr against a tuned reactive incumbent
12-hour plan stability    94.1 % of 21,640 re-plans change nothing at all
```

The ladder, one constraint at a time:

```
N-56-like: notice 0, skill 1.00, no constraint    +44.7 h/yr
+ switch budget 2, min dwell 3 h                +44.7 h/yr
+ dew-point gate 15 C (Green Grid WP#46 p.6)     +92.5 h/yr
+ notice 3 h, skill 0.50 (no perfect forecast)   +279.2 h/yr
+ unanchored, 4 measured FG offsets rotated     -135.2 h/yr
```

PRICED, IN THIS STATE'S OWN ELECTRICITY TARIFF

```
Chiller power            156.1 kW per MW of IT load (0.549 kW/ton, the ASHRAE 90.1-2019 minimum)
Electricity              8.72 cents/kWh (Virginia commercial, 2024 annual)
Energy avoided           43,579 kWh per MW of IT load per year
Value                    $3,800 per MW of IT load per year
```

Everything above is PER MEGAWATT OF IT LOAD. This project has never measured a data centre's size and will not invent one; a reader who knows their own IT load multiplies once.

WHAT IS NOT CLAIMED

- The chiller COMPRESSOR only. Fans, chilled-water pumps, condenser pumps and cooling-tower fans keep running, and an airside economizer moves MORE air, so fan power can rise. The unmeasured term has the OPPOSITE SIGN, so this is an upper bound.
- Code-minimum chiller efficiency is the OPTIMISTIC end: Standard 90.1 is a floor, hyperscale plants beat it, and a better chiller saves less per hour switched off.
- Full-load kW/ton OVERSTATES the draw at the moment free cooling is available, because free cooling happens when it is cool and a chiller at a cool condenser runs below its rating. IPLV is the lower published number but is an annual-weighted metric under AHRI's assumed load profile, not the part-load point free-cooling weather sits at.
- The heat rejected is APPROXIMATED by the IT load. UPS, PDU and lighting losses inside the envelope add to it; some overhead sits outside the cooled space, so scaling by full PUE would overshoot. No PUE multiplier is applied.
- EIA STATE-SECTOR AVERAGES, not the site's tariff. A Loudoun County campus buys on a large-general-service contract that is not public.
- No carbon, no water, no maintenance and no demand charges. Tower water use moves the OTHER way when the chiller runs less.
- Every caveat on the hours is inherited: the headline is conditional on the bank sitting on the long facade (the refusal guard is priced at -3,124 h/yr where it fires) and the unanchored row is NEGATIVE. Those rows appear here with their signs intact.

HOW TO REPRODUCE EVERY NUMBER IN THIS REPORT

```
cd INTAKE-ARBITER/src && python run_all.py
```

That rebuilds every artefact from saved data and then audits it: 39 checks, 68 published figures re-read out of the files the code itself wrote, and it exits non-zero on any failure. It makes ZERO API calls -- every input is a saved FortyGuard response, a committed geometry file, or the station's own hourly record.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.