

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location NJ facility NJ_way_1189426328 -- station KWRI, America/New_York
Building OSM 1189426328
OSM way 1189426328
Facade gap not applicable -- one building, no second facade
Weather record 42,763 real hourly records from KWRI
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs.
Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2024-10-21 (crossing)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 1 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 2 of 24 hours with 1 mode change. The reactive incumbent took 11 hours -- 9 more -- but declared 1 unsafe hour against the agent's 0. The incumbent had to break its own switch budget 1 time to stay safe; the agent never did. 10 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 2 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 11 of 24 hours free cooling, 2 mode change(s), 1 unsafe hour(s)
the incumbent broke its own switch budget 1 time(s) to stay safe
10 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	yes	switch budget	10.780	18.0	10.560	0.903
01	mechanical	yes	switch budget	10.085	18.0	9.110	0.820
02	mechanical	yes	switch budget	9.005	18.0	6.890	0.787
03	mechanical	yes	switch budget	10.085	18.0	8.890	0.804
04	mechanical	yes	switch budget	7.610	18.0	5.390	0.764
05	mechanical	yes	switch budget	6.165	18.0	4.610	0.753
06	mechanical	yes	switch budget	7.110	18.0	3.720	0.880
07	mechanical	yes	switch budget	8.470	18.0	7.220	1.429
08	mechanical	yes	switch budget	13.085	18.0	14.110	1.955
09	mechanical	yes	switch budget	15.220	18.0	17.390	2.207
10	mechanical	no	dry-bulb	18.580	18.0	21.110	2.000
11	mechanical	no	dry-bulb	22.135	18.0	23.110	1.566
12	mechanical	no	dry-bulb	24.360	18.0	25.890	1.227
13	mechanical	no	dry-bulb	26.275	18.0	27.220	1.028

14	mechanical	no	dry-bulb	26.915	18.0	27.500	0.982
15	mechanical	no	dry-bulb	27.865	18.0	27.610	0.959
16	mechanical	no	dry-bulb	27.665	18.0	26.780	1.051
17	mechanical	no	dry-bulb	25.725	18.0	23.500	1.138
18	mechanical	no	dry-bulb	22.970	18.0	18.720	1.208
19	mechanical	no	dry-bulb	22.005	18.0	17.780	1.460
20	mechanical	no	dry-bulb	21.030	18.0	18.890	1.577
21	mechanical	no	dry-bulb	18.250	18.0	17.780	1.484
22	FREE	yes	-	17.310	18.0	16.670	1.209
23	FREE	yes	-	17.110	18.0	15.000	1.008

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.780 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

01:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.085 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

02:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 9.005 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

03:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.085 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 7.610 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 6.165 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 7.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 8.470 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a

mode change here would cost a better one later.

08:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.085 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

09:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.580 C against a 18.0 C limit, so it fails by 0.580 C. It would take a limit 0.580 C higher, or a bound 0.580 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.135 C against a 18.0 C limit, so it fails by 4.135 C. It would take a limit 4.135 C higher, or a bound 4.135 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.360 C against a 18.0 C limit, so it fails by 6.360 C. It would take a limit 6.360 C higher, or a bound 6.360 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.275 C against a 18.0 C limit, so it fails by 8.275 C. It would take a limit 8.275 C higher, or a bound 8.275 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.915 C against a 18.0 C limit, so it fails by 8.915 C. It would take a limit 8.915 C higher, or a bound 8.915 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.865 C against a 18.0 C limit, so it fails by 9.865 C. It would take a limit 9.865 C higher, or a bound 9.865 C tighter, to change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.665 C against a 18.0 C limit, so it fails by 9.665 C. It would take a limit 9.665 C higher, or a bound 9.665 C tighter, to change this hour.

17:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 25.725 C against a 18.0 C limit, so it fails by 7.725 C. It would take a limit 7.725 C higher, or a bound 7.725 C tighter, to change this hour.

18:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.970 C against a 18.0 C limit, so it fails by 4.970 C. It would take a limit 4.970 C higher, or a bound 4.970 C tighter, to change this hour.

19:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.005 C against a 18.0 C limit, so it fails by 4.005 C. It would take a limit 4.005 C higher, or a bound 4.005 C tighter, to change this hour.

20:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.030 C against a 18.0 C limit, so it fails by 3.030 C. It would take a limit 3.030 C higher, or a bound 3.030 C tighter, to change this hour.

21:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.250 C against a 18.0 C limit, so it fails by 0.250 C. It would take a limit 0.250 C higher, or a bound 0.250 C tighter, to change this hour.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.310 C, which is 0.690 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.209 C, and the margin is measured, not chosen: 1.209 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.110 C, which is 0.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.008 C, and the margin is measured, not chosen: 1.008 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

WHAT IT IS WORTH OVER FIVE REAL YEARS, AT THIS SITE

Held-out days simulated 909 -- the agent never calibrates on a day it is scored on
Free cooling delivered 14.80 h/day, i.e. 5,405 h/yr
Chiller-hours avoided +395.0 h/yr against a tuned reactive incumbent
12-hour plan stability 94.1 % of 21,260 re-plans change nothing at all

The ladder, one constraint at a time:

N-56-like: notice 0, skill 1.00, no constraint +64.3 h/yr
+ switch budget 2, min dwell 3 h +94.8 h/yr
+ dew-point gate 15 C (Green Grid WP#46 p.6) +101.3 h/yr
+ notice 3 h, skill 0.50 (no perfect forecast) +395.0 h/yr
+ unanchored, 4 measured FG offsets rotated -131.4 h/yr

PRICED, IN THIS STATE'S OWN ELECTRICITY TARIFF

Chiller power 156.1 kW per MW of IT load (0.549 kW/ton, the ASHRAE 90.1-2019 minimum)
Electricity 8.72 cents/kWh (Virginia commercial, 2024 annual)
Energy avoided 61,659 kWh per MW of IT load per year
Value \$5,377 per MW of IT load per year

Everything above is PER MEGAWATT OF IT LOAD. This project has never measured a data centre's size and will not invent one; a reader who knows their own IT load multiplies once.

WHAT IS NOT CLAIMED

- The chiller COMPRESSOR only. Fans, chilled-water pumps, condenser pumps and cooling-tower fans keep running, and an airside economizer moves MORE air, so fan power can rise. The unmeasured term has the OPPOSITE SIGN, so this is an upper bound.
- Code-minimum chiller efficiency is the OPTIMISTIC end: Standard 90.1 is a floor, hyperscale plants beat it, and a better chiller saves less per hour switched off.
- Full-load kW/ton OVERSTATES the draw at the moment free cooling is available, because free cooling happens when it is cool and a chiller at a cool condenser runs below its rating. IPLV is the lower published number but is an annual-weighted metric under AHRI's assumed load profile, not the part-load point free-cooling weather sits at.
- The heat rejected is APPROXIMATED by the IT load. UPS, PDU and lighting losses inside the envelope add to it; some overhead sits outside the cooled space, so scaling by full PUE would overshoot. No PUE multiplier is applied.
- EIA STATE-SECTOR AVERAGES, not the site's tariff. A Loudoun County campus buys on a large-general-service contract that is not public.
- No carbon, no water, no maintenance and no demand charges. Tower water use moves the OTHER way when the chiller runs less.
- Every caveat on the hours is inherited: the headline is conditional on the bank sitting on the long facade (the refusal guard is priced at -3,124 h/yr where it fires) and the unanchored row is NEGATIVE. Those rows appear here with their signs intact.

HOW TO REPRODUCE EVERY NUMBER IN THIS REPORT

```
cd INTAKE-ARBITER/src && python run_all.py
```

That rebuilds every artefact from saved data and then audits it: 39 checks, 68 published figures re-read out of the files the code itself wrote, and it exits non-zero on any failure. It makes ZERO API calls -- every input is a saved FortyGuard response, a committed geometry file, or the station's own hourly record.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.