

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location Lumen Dallas 6, TX -- station KDAL, America/Chicago
Building OSM 465032484
Lumen Dallas 6
Facade gap not applicable -- one building, no second facade
Weather record 43,803 real hourly records from KDAL
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs.

Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2022-01-01 (crossing)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point gate off

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 10 of 24 hours with 1 mode change. That is 9 more than the reactive incumbent, at 0 unsafe hours against its 1. The incumbent had to break its own switch budget 1 time to stay safe; the agent never did. 4 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 10 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 1 of 24 hours free cooling, 2 mode change(s), 1 unsafe hour(s)
the incumbent broke its own switch budget 1 time(s) to stay safe
4 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	no	dry-bulb	18.055	18.0	18.330	0.688
01	mechanical	no	dry-bulb	18.330	18.0	18.330	0.877
02	mechanical	no	dry-bulb	18.055	18.0	17.780	0.801
03	mechanical	no	dry-bulb	18.055	18.0	17.780	0.723
04	mechanical	yes	switch budget	17.775	18.0	17.220	0.664
05	mechanical	yes	switch budget	17.225	18.0	16.670	0.589
06	mechanical	yes	switch budget	17.500	18.0	16.670	0.734
07	mechanical	yes	switch budget	17.500	18.0	16.670	0.622
08	mechanical	no	dry-bulb	18.610	18.0	16.670	1.226
09	mechanical	no	dry-bulb	20.000	18.0	17.220	1.540
10	mechanical	no	dry-bulb	21.670	18.0	19.440	1.544
11	mechanical	no	dry-bulb	22.225	18.0	20.560	1.497
12	mechanical	no	dry-bulb	22.775	18.0	21.670	1.392
13	mechanical	no	dry-bulb	23.885	18.0	22.780	1.157

14	FREE	yes	-	17.780	18.0	10.560	0.979
15	FREE	yes	-	15.555	18.0	6.110	0.851
16	FREE	yes	-	14.165	18.0	3.330	0.797
17	FREE	yes	-	6.945	18.0	2.220	0.826
18	FREE	yes	-	3.335	18.0	0.560	0.805
19	FREE	yes	-	1.085	18.0	-0.610	0.947
20	FREE	yes	-	-0.030	18.0	-1.720	1.087
21	FREE	yes	-	-1.390	18.0	-2.780	1.034
22	FREE	yes	-	-2.525	18.0	-3.890	0.894
23	FREE	yes	-	-3.635	18.0	-5.000	0.765

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.055 C against a 18.0 C limit, so it fails by 0.055 C. It would take a limit 0.055 C higher, or a bound 0.055 C tighter, to change this hour.

01:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.330 C against a 18.0 C limit, so it fails by 0.330 C. It would take a limit 0.330 C higher, or a bound 0.330 C tighter, to change this hour.

02:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.055 C against a 18.0 C limit, so it fails by 0.055 C. It would take a limit 0.055 C higher, or a bound 0.055 C tighter, to change this hour.

03:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.055 C against a 18.0 C limit, so it fails by 0.055 C. It would take a limit 0.055 C higher, or a bound 0.055 C tighter, to change this hour.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.775 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.225 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.500 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.500 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.610 C against a 18.0 C limit, so it fails by 0.610 C. It would take a limit 0.610 C higher, or a bound 0.610 C tighter, to change this hour.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.000 C against a 18.0 C limit, so it fails by 2.000 C. It would take a limit 2.000 C higher, or a bound 2.000 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.670 C against a 18.0 C limit, so it fails by 3.670 C. It would take a limit 3.670 C higher, or a bound 3.670 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.225 C against a 18.0 C limit, so it fails by 4.225 C. It would take a limit 4.225 C higher, or a bound 4.225 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.775 C against a 18.0 C limit, so it fails by 4.775 C. It would take a limit 4.775 C higher, or a bound 4.775 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.885 C against a 18.0 C limit, so it fails by 5.885 C. It would take a limit 5.885 C higher, or a bound 5.885 C tighter, to change this hour.

14:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.780 C, which is 0.220 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.979 C, and the margin is measured, not chosen: 0.979 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

15:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.555 C, which is 2.445 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.851 C, and the margin is measured, not chosen: 0.851 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

16:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.165 C, which is 3.835 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.797 C, and the margin is measured, not chosen: 0.797 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

17:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.945 C, which is 11.055 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.826 C, and the margin is measured, not chosen: 0.826 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

18:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 3.335 C, which is 14.665 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.805 C, and the margin is measured, not chosen: 0.805 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

19:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 1.085 C, which is 16.915 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.947 C, and the margin is measured, not chosen: 0.947 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

20:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is -0.030 C, which is 18.030 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.086 C, and the margin is measured, not chosen: 1.086 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

21:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is -1.390 C, which is 19.390 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.034 C, and the margin is measured, not chosen: 1.034 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is -2.525 C, which is 20.525 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.894 C, and the margin is measured, not chosen: 0.894 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is -3.635 C, which is 21.635 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.765 C, and the margin is measured, not chosen: 0.765 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

WHAT IT IS WORTH OVER FIVE REAL YEARS, AT THIS SITE

Held-out days simulated 913 -- the agent never calibrates on a day it is scored on
Free cooling delivered 9.43 h/day, i.e. 3,443 h/yr
Chiller-hours avoided +332.8 h/yr against a tuned reactive incumbent
12-hour plan stability 94.6 % of 21,901 re-plans change nothing at all

The ladder, one constraint at a time:

N-56-like: notice 0, skill 1.00, no constraint +67.6 h/yr
+ switch budget 2, min dwell 3 h +98.4 h/yr
+ dew-point gate 15 C (Green Grid WP#46 p.6) +140.0 h/yr
+ notice 3 h, skill 0.50 (no perfect forecast) +332.8 h/yr
+ unanchored, 4 measured FG offsets rotated -183.6 h/yr

PRICED, IN THIS STATE'S OWN ELECTRICITY TARIFF

Chiller power 156.1 kW per MW of IT load (0.549 kW/ton, the ASHRAE 90.1-2019 minimum)
Electricity 8.72 cents/kWh (Virginia commercial, 2024 annual)
Energy avoided 51,959 kWh per MW of IT load per year
Value \$4,531 per MW of IT load per year

Everything above is PER MEGAWATT OF IT LOAD. This project has never measured a data centre's size and will not invent one; a reader who knows their own IT load multiplies once.

WHAT IS NOT CLAIMED

- The chiller COMPRESSOR only. Fans, chilled-water pumps, condenser pumps and cooling-tower fans keep running, and an airside economizer moves MORE air, so fan power can rise. The unmeasured term has the OPPOSITE SIGN, so this is an upper bound.
- Code-minimum chiller efficiency is the OPTIMISTIC end: Standard 90.1 is a floor, hyperscale plants beat it, and a better chiller saves less per hour switched off.
- Full-load kW/ton OVERSTATES the draw at the moment free cooling is available, because free cooling happens when it is cool and a chiller at a cool condenser runs below its rating. IPLV is the lower published number but is an annual-weighted metric under AHRI's assumed load profile, not the part-load point free-cooling weather sits at.
- The heat rejected is APPROXIMATED by the IT load. UPS, PDU and lighting losses inside the envelope add to it; some overhead sits outside the cooled space, so scaling by full PUE would overshoot. No PUE multiplier is applied.
- EIA STATE-SECTOR AVERAGES, not the site's tariff. A Loudoun County campus buys on a large-general-service contract that is not public.
- No carbon, no water, no maintenance and no demand charges. Tower water use moves the OTHER way when the chiller runs less.
- Every caveat on the hours is inherited: the headline is conditional on the bank sitting on the long facade (the refusal guard is priced at -3,124 h/yr where it fires) and the unanchored row is NEGATIVE. Those rows appear here with their signs intact.

HOW TO REPRODUCE EVERY NUMBER IN THIS REPORT

```
cd INTAKE-ARBITER/src && python run_all.py
```

That rebuilds every artefact from saved data and then audits it: 39 checks, 68 published figures re-read out of the files the code itself wrote, and it exits non-zero on any failure. It makes ZERO API calls -- every input is a saved FortyGuard response, a committed geometry file, or the station's own hourly record.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.