

# INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

## THE SITE

Location VA facility VA\_way\_260996040 -- station KDAA, America/New\_York  
Building OSM 260996040  
OSM way 260996040  
Facade gap not applicable -- one building, no second facade  
Weather record 42,250 real hourly records from KDAA  
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs.

Quote the hours for this site; quote the coverage for Ashburn.

## THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2023-06-12 (chatter)  
Plant limit 21.0 C  
Notice required 3 h  
Forecast skill 0.50 relative to persistence  
Level anchor sensor  
Condenser bank longest facade  
Switch budget 2 mode changes per day  
Minimum dwell 3 h  
Max dew point 15.0 C (Green Grid WP#46 p.6)

## WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 1 of 23 hours with 1 mode change. That is 1 more than the reactive incumbent, at 0 unsafe hours against its 0.

Agent 1 of 23 hours free cooling, 1 mode change(s), 0 unsafe hour(s)  
Incumbent 0 of 23 hours free cooling, 0 mode change(s), 0 unsafe hour(s)

## EVERY HOUR, AND THE REASON FOR IT

| hh | mode       | safe | binding   | bound  | limit | actual | margin |
|----|------------|------|-----------|--------|-------|--------|--------|
| 00 | mechanical | no   | dry-bulb  | 24.360 | 21.0  | 24.220 | 0.949  |
| 01 | mechanical | no   | dry-bulb  | 24.250 | 21.0  | 23.720 | 0.911  |
| 02 | mechanical | no   | dry-bulb  | 24.110 | 21.0  | 23.330 | 0.872  |
| 04 | mechanical | no   | dew point | 23.195 | 21.0  | 21.390 | 0.840  |
| 05 | mechanical | no   | dew point | 22.695 | 21.0  | 20.780 | 0.848  |
| 06 | mechanical | no   | dew point | 23.275 | 21.0  | 22.000 | 0.851  |
| 07 | mechanical | no   | dew point | 23.835 | 21.0  | 22.390 | 1.447  |
| 08 | mechanical | no   | dry-bulb  | 26.415 | 21.0  | 24.440 | 2.067  |
| 09 | mechanical | no   | dry-bulb  | 28.055 | 21.0  | 24.000 | 2.437  |
| 10 | mechanical | no   | dry-bulb  | 28.610 | 21.0  | 24.000 | 2.686  |
| 11 | mechanical | no   | dry-bulb  | 28.195 | 21.0  | 23.780 | 1.957  |
| 12 | mechanical | no   | dry-bulb  | 27.165 | 21.0  | 24.440 | 1.316  |
| 13 | mechanical | no   | dry-bulb  | 26.110 | 21.0  | 23.610 | 1.098  |
| 14 | mechanical | no   | dew point | 25.115 | 21.0  | 22.780 | 0.975  |
| 15 | mechanical | no   | dew point | 25.165 | 21.0  | 23.110 | 0.926  |
| 16 | mechanical | no   | dew point | 25.140 | 21.0  | 24.780 | 1.006  |
| 17 | mechanical | no   | dew point | 24.390 | 21.0  | 25.000 | 1.200  |
| 18 | mechanical | no   | dew point | 22.390 | 21.0  | 21.670 | 1.369  |
| 19 | mechanical | no   | dew point | 23.250 | 21.0  | 22.390 | 1.514  |

|    |            |     |           |        |      |        |       |
|----|------------|-----|-----------|--------|------|--------|-------|
| 20 | mechanical | no  | dew point | 22.970 | 21.0 | 21.500 | 1.764 |
| 21 | mechanical | no  | dew point | 20.975 | 21.0 | 20.560 | 1.668 |
| 22 | mechanical | no  | dew point | 21.250 | 21.0 | 20.220 | 1.360 |
| 23 | FREE       | yes | -         | 20.280 | 21.0 | 18.890 | 1.112 |

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

## THE REASONING, HOUR BY HOUR

### 00:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.360 C against a 21.0 C limit, so it fails by 3.360 C. It would take a limit 3.360 C higher, or a bound 3.360 C tighter, to change this hour.

### 01:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.250 C against a 21.0 C limit, so it fails by 3.250 C. It would take a limit 3.250 C higher, or a bound 3.250 C tighter, to change this hour.

### 02:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.110 C against a 21.0 C limit, so it fails by 3.110 C. It would take a limit 3.110 C higher, or a bound 3.110 C tighter, to change this hour.

### 04:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 23.195 C would have passed. The outside air is too HUMID: the dew-point bound is 17.25 C against a 15.0 C maximum, failing by 2.25 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

### 05:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 22.695 C would have passed. The outside air is too HUMID: the dew-point bound is 17.55 C against a 15.0 C maximum, failing by 2.55 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

### 06:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 23.275 C would have passed. The outside air is too HUMID: the dew-point bound is 18.26 C against a 15.0 C maximum, failing by 3.26 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

### 07:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 23.835 C would have passed. The outside air is too HUMID: the dew-point bound is 19.11 C against a 15.0 C maximum, failing by 4.11 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

### 08:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.415 C against a 21.0 C limit, so it fails by 5.415 C. It would take a limit 5.415 C higher, or a bound 5.415 C tighter, to change this hour.

### 09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 28.055 C against a 21.0 C limit, so it fails by 7.055 C. It would take a limit 7.055 C higher, or a bound 7.055 C tighter, to change this hour.

### 10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 28.610 C against a 21.0 C limit, so it fails by 7.610 C. It would take a limit 7.610 C higher, or a bound 7.610 C tighter, to change this hour.

### 11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 28.195 C against a 21.0 C limit, so it fails by 7.195 C. It would take a limit 7.195 C higher, or a bound 7.195 C tighter, to change this hour.

### 12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.165 C against a 21.0 C limit, so it fails by 6.165 C. It would take a limit 6.165 C higher, or a bound 6.165 C tighter, to change this hour.

### 13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.110 C against a 21.0 C limit, so it fails by 5.110 C. It would take a limit 5.110 C higher, or a bound 5.110 C tighter, to change this hour.

### 14:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 25.115 C would have passed. The outside air is too HUMID: the dew-point bound is 20.89 C against a 15.0 C maximum, failing by 5.89 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 15:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 25.165 C would have passed.  
The outside air is too HUMID: the dew-point bound is 21.30 C against a 15.0 C maximum, failing by 6.30 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 16:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 25.140 C would have passed.  
The outside air is too HUMID: the dew-point bound is 21.73 C against a 15.0 C maximum, failing by 6.73 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 17:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 24.390 C would have passed.  
The outside air is too HUMID: the dew-point bound is 20.86 C against a 15.0 C maximum, failing by 5.86 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 18:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 22.390 C would have passed.  
The outside air is too HUMID: the dew-point bound is 21.55 C against a 15.0 C maximum, failing by 6.55 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 19:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 23.250 C would have passed.  
The outside air is too HUMID: the dew-point bound is 20.53 C against a 15.0 C maximum, failing by 5.53 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 20:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 22.970 C would have passed.  
The outside air is too HUMID: the dew-point bound is 17.39 C against a 15.0 C maximum, failing by 2.39 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 21:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 20.975 C would have passed.  
The outside air is too HUMID: the dew-point bound is 16.70 C against a 15.0 C maximum, failing by 1.70 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 22:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 21.250 C would have passed.  
The outside air is too HUMID: the dew-point bound is 15.50 C against a 15.0 C maximum, failing by 0.50 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

#### 23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 20.280 C, which is 0.720 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.112 C, and the margin is measured, not chosen: 1.112 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

### WHAT IT IS WORTH OVER FIVE REAL YEARS, AT THIS SITE

---

|                         |                                                            |
|-------------------------|------------------------------------------------------------|
| Held-out days simulated | 905 -- the agent never calibrates on a day it is scored on |
| Free cooling delivered  | 13.34 h/day, i.e. 4,872 h/yr                               |
| Chiller-hours avoided   | +383.4 h/yr against a tuned reactive incumbent             |
| 12-hour plan stability  | 95.0 % of 20,901 re-plans change nothing at all            |

#### The ladder, one constraint at a time:

|                                                |             |
|------------------------------------------------|-------------|
| N-56-like: notice 0, skill 1.00, no constraint | +62.6 h/yr  |
| + switch budget 2, min dwell 3 h               | +97.3 h/yr  |
| + dew-point gate 15 C (Green Grid WP#46 p.6)   | +107.4 h/yr |
| + notice 3 h, skill 0.50 (no perfect forecast) | +383.4 h/yr |
| + unanchored, 4 measured FG offsets rotated    | -132.8 h/yr |

### PRICED, IN THIS STATE'S OWN ELECTRICITY TARIFF

---

|               |                                                                         |
|---------------|-------------------------------------------------------------------------|
| Chiller power | 156.1 kW per MW of IT load (0.549 kW/ton, the ASHRAE 90.1-2019 minimum) |
| Electricity   | 8.72 cents/kWh (Virginia commercial, 2024 annual)                       |

|                |                                       |
|----------------|---------------------------------------|
| Energy avoided | 59,853 kwh per MW of IT load per year |
| Value          | \$5,219 per MW of IT load per year    |

Everything above is PER MEGAWATT OF IT LOAD. This project has never measured a data centre's size and will not invent one; a reader who knows their own IT load multiplies once.

## WHAT IS NOT CLAIMED

- The chiller COMPRESSOR only. Fans, chilled-water pumps, condenser pumps and cooling-tower fans keep running, and an airside economizer moves MORE air, so fan power can rise. The unmeasured term has the OPPOSITE SIGN, so this is an upper bound.
- Code-minimum chiller efficiency is the OPTIMISTIC end: Standard 90.1 is a floor, hyperscale plants beat it, and a better chiller saves less per hour switched off.
- Full-load kW/ton OVERSTATES the draw at the moment free cooling is available, because free cooling happens when it is cool and a chiller at a cool condenser runs below its rating. IPLV is the lower published number but is an annual-weighted metric under AHRI's assumed load profile, not the part-load point free-cooling weather sits at.
- The heat rejected is APPROXIMATED by the IT load. UPS, PDU and lighting losses inside the envelope add to it; some overhead sits outside the cooled space, so scaling by full PUE would overshoot. No PUE multiplier is applied.
- EIA STATE-SECTOR AVERAGES, not the site's tariff. A Loudoun County campus buys on a large-general-service contract that is not public.
- No carbon, no water, no maintenance and no demand charges. Tower water use moves the OTHER way when the chiller runs less.
- Every caveat on the hours is inherited: the headline is conditional on the bank sitting on the long facade (the refusal guard is priced at -3,124 h/yr where it fires) and the unanchored row is NEGATIVE. Those rows appear here with their signs intact.

## HOW TO REPRODUCE EVERY NUMBER IN THIS REPORT

```
cd INTAKE-ARBITER/src && python run_all.py
```

That rebuilds every artefact from saved data and then audits it: 39 checks, 68 published figures re-read out of the files the code itself wrote, and it exits non-zero on any failure. It makes ZERO API calls -- every input is a saved FortyGuard response, a committed geometry file, or the station's own hourly record.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.