

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location BB&T Data Center, NC -- station KLHZ, America/New_York
Building OSM 830138727
BB&T Data Center
Facade gap not applicable -- one building, no second facade
Weather record 43,284 real hourly records from KLHZ
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-02-28 (chatter)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 13 of 24 hours with 2 mode changes. That is 4 more than the reactive incumbent, at 0 unsafe hours against its 0.

Agent 13 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 9 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	10.000	18.0	10.000	0.691
01	FREE	yes	-	9.500	18.0	9.000	0.637
02	FREE	yes	-	9.500	18.0	9.000	0.623
03	FREE	yes	-	10.000	18.0	10.000	0.578
04	FREE	yes	-	9.500	18.0	10.000	0.543
05	FREE	yes	-	10.000	18.0	10.000	0.957

06	FREE	yes	-	10.500	18.0	10.000	0.805
07	FREE	yes	-	12.000	18.0	11.000	1.224
08	FREE	yes	-	13.500	18.0	11.000	1.650
09	FREE	yes	-	15.500	18.0	12.000	2.149
10	FREE	yes	-	17.000	18.0	13.000	2.289
11	FREE	yes	-	17.500	18.0	16.000	1.604
12	FREE	yes	-	17.500	18.0	17.000	1.108
13	mechanical	no	dry-bulb	19.000	18.0	20.000	1.062
14	mechanical	no	dry-bulb	21.000	18.0	22.000	1.007
15	mechanical	no	dry-bulb	21.000	18.0	22.000	0.955
16	mechanical	no	dry-bulb	22.000	18.0	22.000	1.066
17	mechanical	no	dry-bulb	22.000	18.0	21.000	1.250
18	mechanical	no	dew point	20.000	18.0	18.000	1.456
19	mechanical	no	dew point	20.000	18.0	19.000	1.473
20	mechanical	no	dew point	19.000	18.0	18.000	1.584
21	mechanical	no	dew point	19.000	18.0	20.000	1.762
22	mechanical	no	dew point	18.500	18.0	18.000	1.224
23	mechanical	no	dew point	18.500	18.0	19.000	0.820

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin
actual = what the intake temperature turned out to be, from the station record
margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.000 C, which is 8.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.691 C, and the margin is measured, not chosen: 0.691 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.500 C, which is 8.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.638 C, and the margin is measured, not chosen: 0.638 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.500 C, which is 8.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.623 C, and the margin is measured, not chosen: 0.623 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.000 C, which is 8.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.577 C, and the margin is measured, not chosen: 0.577 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.500 C, which is 8.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.543 C, and the margin is measured, not chosen: 0.543 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.000 C, which is 8.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.957 C, and

the margin is measured, not chosen: 0.957 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.500 C, which is 7.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.805 C, and the margin is measured, not chosen: 0.805 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.000 C, which is 6.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.224 C, and the margin is measured, not chosen: 1.224 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.500 C, which is 4.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.650 C, and the margin is measured, not chosen: 1.650 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

09:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.500 C, which is 2.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.149 C, and the margin is measured, not chosen: 2.149 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

10:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.000 C, which is 1.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.289 C, and the margin is measured, not chosen: 2.289 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

11:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.500 C, which is 0.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.604 C, and the margin is measured, not chosen: 1.604 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

12:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.500 C, which is 0.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.108 C, and the margin is measured, not chosen: 1.108 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.000 C against a 18.0 C limit, so it fails by 1.000 C. It would take a limit 1.000 C higher, or a bound 1.000 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.000 C against a 18.0 C limit, so it fails by 3.000 C. It would take a limit 3.000 C higher, or a bound 3.000 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.000 C against a 18.0 C limit, so it fails by 3.000 C. It would take a limit 3.000 C higher, or a bound 3.000 C tighter, to

change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.000 C against a 18.0 C limit, so it fails by 4.000 C. It would take a limit 4.000 C higher, or a bound 4.000 C tighter, to change this hour.

17:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.000 C against a 18.0 C limit, so it fails by 4.000 C. It would take a limit 4.000 C higher, or a bound 4.000 C tighter, to change this hour.

18:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 20.000 C would have passed. The outside air is too HUMID: the dew-point bound is 18.00 C against a 15.0 C maximum, failing by 3.00 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

19:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 20.000 C would have passed. The outside air is too HUMID: the dew-point bound is 18.00 C against a 15.0 C maximum, failing by 3.00 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

20:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 19.000 C would have passed. The outside air is too HUMID: the dew-point bound is 17.50 C against a 15.0 C maximum, failing by 2.50 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

21:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 19.000 C would have passed. The outside air is too HUMID: the dew-point bound is 17.50 C against a 15.0 C maximum, failing by 2.50 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

22:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 18.500 C would have passed. The outside air is too HUMID: the dew-point bound is 17.00 C against a 15.0 C maximum, failing by 2.00 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

23:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 18.500 C would have passed. The outside air is too HUMID: the dew-point bound is 16.50 C against a 15.0 C maximum, failing by 1.50 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.