

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location Information Systems Facility, NM -- station KELP, America/Denver
Building OSM 1519367009
Information Systems Facility
Facade gap not applicable -- one building, no second facade
Weather record 43,804 real hourly records from KELP
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2023-01-12 (clear_cool)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 13 of 24 hours with 2 mode changes. 8 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 13 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 13 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
8 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	5.220	18.0	8.000	3.282
01	FREE	yes	-	5.780	18.0	8.000	3.183
02	FREE	yes	-	6.330	18.0	8.000	3.237
03	FREE	yes	-	6.340	18.0	6.000	2.930

04	FREE	yes	-	6.880	18.0	6.000	3.160
05	FREE	yes	-	6.890	18.0	4.000	2.880
06	FREE	yes	-	6.890	18.0	2.000	2.431
07	FREE	yes	-	9.110	18.0	4.000	2.512
08	FREE	yes	-	11.890	18.0	6.000	2.503
09	FREE	yes	-	13.720	18.0	9.000	3.617
10	FREE	yes	-	16.560	18.0	10.000	3.996
11	FREE	yes	-	17.330	18.0	12.000	4.612
12	FREE	yes	-	17.000	18.0	13.000	4.681
13	mechanical	no	dry-bulb	18.440	18.0	13.000	4.544
14	mechanical	no	dry-bulb	18.220	18.0	14.000	3.784
15	mechanical	no	dry-bulb	18.450	18.0	14.000	2.837
16	mechanical	yes	switch budget	17.220	18.0	14.000	2.855
17	mechanical	yes	switch budget	17.000	18.0	12.000	3.236
18	mechanical	yes	switch budget	15.220	18.0	8.000	2.935
19	mechanical	yes	switch budget	13.000	18.0	8.000	3.088
20	mechanical	yes	switch budget	11.780	18.0	6.000	2.700
21	mechanical	yes	switch budget	10.670	18.0	5.000	2.791
22	mechanical	yes	switch budget	10.110	18.0	4.000	2.758
23	mechanical	yes	switch budget	8.660	18.0	4.000	3.145

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin
actual = what the intake temperature turned out to be, from the station record
margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 5.220 C, which is 12.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.282 C, and the margin is measured, not chosen: 3.282 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 5.780 C, which is 12.220 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.183 C, and the margin is measured, not chosen: 3.183 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.330 C, which is 11.670 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.237 C, and the margin is measured, not chosen: 3.237 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.340 C, which is 11.660 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.930 C, and the margin is measured, not chosen: 2.930 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.880 C, which is 11.120 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.160 C, and the margin is measured, not chosen: 3.160 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.890 C, which is 11.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.880 C, and the margin is measured, not chosen: 2.880 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 6.890 C, which is 11.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.431 C, and the margin is measured, not chosen: 2.431 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.110 C, which is 8.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.512 C, and the margin is measured, not chosen: 2.512 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.890 C, which is 6.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.503 C, and the margin is measured, not chosen: 2.503 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

09:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.720 C, which is 4.280 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.617 C, and the margin is measured, not chosen: 3.617 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

10:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.560 C, which is 1.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.996 C, and the margin is measured, not chosen: 3.996 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

11:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.330 C, which is 0.670 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.612 C, and the margin is measured, not chosen: 4.612 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

12:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.000 C, which is 1.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.681 C, and the margin is measured, not chosen: 4.681 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.440 C against a 18.0 C limit, so it fails by 0.440 C. It would take a limit 0.440 C higher, or a bound 0.440 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.220 C against a 18.0 C limit, so it fails by 0.220 C. It would take a limit 0.220 C higher, or a bound 0.220 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.450 C against a 18.0 C limit, so it fails by 0.450 C. It would take a limit 0.450 C higher, or a bound 0.450 C tighter, to change this hour.

16:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

17:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

18:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

19:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

20:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 11.780 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

21:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.670 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

22:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

23:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 8.660 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is

also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.