

AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location Serverfarm CH1, IL -- station KMDW, America/Chicago
Building OSM 152449872
Serverfarm CH1
Facade gap not applicable -- one building, no second facade
Weather record 43,808 real hourly records from KMDW
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-11-09 (clear_cool)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 9 of 24 hours with 2 mode changes. 8 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 9 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 9 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
8 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	10.560	18.0	10.560	2.933
01	FREE	yes	-	10.560	18.0	10.560	2.617
02	FREE	yes	-	10.560	18.0	11.110	2.380
03	FREE	yes	-	10.560	18.0	13.330	2.239
04	FREE	yes	-	11.110	18.0	12.780	2.646

05	FREE	yes	-	11.110	18.0	12.220	2.362
06	FREE	yes	-	11.670	18.0	12.220	2.370
07	FREE	yes	-	12.780	18.0	13.330	2.359
08	FREE	yes	-	15.550	18.0	13.890	3.099
09	mechanical	no	dry-bulb	19.990	18.0	13.330	3.850
10	mechanical	no	dry-bulb	21.110	18.0	13.330	4.235
11	mechanical	no	dry-bulb	22.220	18.0	13.330	4.935
12	mechanical	no	dry-bulb	22.770	18.0	12.780	5.089
13	mechanical	no	dry-bulb	23.330	18.0	13.330	4.909
14	mechanical	no	dry-bulb	22.220	18.0	13.890	4.277
15	mechanical	no	dry-bulb	19.440	18.0	12.220	3.354
16	mechanical	yes	switch budget	17.780	18.0	11.670	3.088
17	mechanical	yes	switch budget	16.110	18.0	11.110	2.809
18	mechanical	yes	switch budget	13.900	18.0	10.000	2.389
19	mechanical	yes	switch budget	13.880	18.0	10.000	2.885
20	mechanical	yes	switch budget	13.890	18.0	8.890	3.016
21	mechanical	yes	switch budget	12.220	18.0	7.780	3.328
22	mechanical	yes	switch budget	11.670	18.0	6.110	3.364
23	mechanical	yes	switch budget	11.110	18.0	6.110	3.229

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.560 C, which is 7.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.934 C, and the margin is measured, not chosen: 2.934 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.560 C, which is 7.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.617 C, and the margin is measured, not chosen: 2.617 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.560 C, which is 7.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.380 C, and the margin is measured, not chosen: 2.380 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.560 C, which is 7.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.239 C, and the margin is measured, not chosen: 2.239 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.110 C, which is 6.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.646 C, and the margin is measured, not chosen: 2.646 C of group-conditional forecast error for this

hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.110 C, which is 6.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.362 C, and the margin is measured, not chosen: 2.362 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.670 C, which is 6.330 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.370 C, and the margin is measured, not chosen: 2.370 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.780 C, which is 5.220 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.359 C, and the margin is measured, not chosen: 2.359 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.550 C, which is 2.450 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.099 C, and the margin is measured, not chosen: 3.099 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.990 C against a 18.0 C limit, so it fails by 1.990 C. It would take a limit 1.990 C higher, or a bound 1.990 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.110 C against a 18.0 C limit, so it fails by 3.110 C. It would take a limit 3.110 C higher, or a bound 3.110 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.220 C against a 18.0 C limit, so it fails by 4.220 C. It would take a limit 4.220 C higher, or a bound 4.220 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.770 C against a 18.0 C limit, so it fails by 4.770 C. It would take a limit 4.770 C higher, or a bound 4.770 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.330 C against a 18.0 C limit, so it fails by 5.330 C. It would take a limit 5.330 C higher, or a bound 5.330 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.220 C against a 18.0 C limit, so it fails by 4.220 C. It would take a limit 4.220 C higher, or a bound 4.220 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.440 C against a 18.0 C limit, so it fails by 1.440 C. It would take a limit 1.440 C higher, or a bound 1.440 C tighter, to change this hour.

16:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.780 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

17:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

18:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.900 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

19:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.880 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

20:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.890 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

21:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

22:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 11.670 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

23:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 11.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision

is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.