

AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location MI facility MI_way_1545590995 -- station KBEH, America/Detroit
Building OSM 1545590995
OSM way 1545590995
Facade gap not applicable -- one building, no second facade
Weather record 42,253 real hourly records from KBEH
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-05-04 (clear_cool)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 10 of 24 hours with 1 mode change. 10 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 10 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 10 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
10 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	yes	switch budget	13.890	18.0	13.890	3.643
01	mechanical	yes	switch budget	14.450	18.0	7.780	3.718
02	mechanical	yes	switch budget	15.000	18.0	7.780	3.555
03	mechanical	yes	switch budget	15.000	18.0	7.780	3.012
04	mechanical	yes	switch budget	15.000	18.0	8.330	2.782

05	mechanical	yes	switch budget	15.000	18.0	8.330	2.612
06	mechanical	yes	switch budget	15.000	18.0	7.220	2.418
07	mechanical	yes	switch budget	10.010	18.0	7.220	2.735
08	mechanical	yes	switch budget	12.780	18.0	7.220	4.004
09	mechanical	yes	switch budget	15.560	18.0	10.000	5.243
10	mechanical	no	dry-bulb	18.330	18.0	9.440	6.118
11	mechanical	no	dry-bulb	20.000	18.0	8.330	6.820
12	mechanical	no	dry-bulb	20.000	18.0	8.330	7.257
13	mechanical	no	dry-bulb	19.440	18.0	8.890	6.828
14	FREE	yes	-	16.670	18.0	8.890	5.117
15	FREE	yes	-	17.220	18.0	10.000	4.210
16	FREE	yes	-	14.440	18.0	8.890	3.298
17	FREE	yes	-	11.670	18.0	8.330	2.787
18	FREE	yes	-	10.550	18.0	9.440	2.780
19	FREE	yes	-	10.000	18.0	8.890	2.859
20	FREE	yes	-	8.890	18.0	8.330	2.907
21	FREE	yes	-	10.000	18.0	7.780	3.663
22	FREE	yes	-	8.890	18.0	7.780	3.937
23	FREE	yes	-	8.330	18.0	7.220	3.914

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.890 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

01:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.450 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

02:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

03:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot

give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.010 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.780 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

09:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.560 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.330 C against a 18.0 C limit, so it fails by 0.330 C. It would take a limit 0.330 C higher, or a bound 0.330 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.000 C against a 18.0 C limit, so it fails by 2.000 C. It would take a limit 2.000 C higher, or a bound 2.000 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.000 C against a 18.0 C limit, so it fails by 2.000 C. It would take a limit 2.000 C higher, or a bound 2.000 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.440 C against a 18.0 C limit, so it fails by 1.440 C. It would take a limit 1.440 C higher, or a bound 1.440 C tighter, to change this hour.

14:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.670 C, which is 1.330 C

under the 18.0 C plant limit. That bound is the forecast plus a margin of 5.117 C, and the margin is measured, not chosen: 5.117 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

15:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.220 C, which is 0.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.210 C, and the margin is measured, not chosen: 4.210 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

16:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.440 C, which is 3.560 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.298 C, and the margin is measured, not chosen: 3.298 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

17:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.670 C, which is 6.330 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.787 C, and the margin is measured, not chosen: 2.787 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

18:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.550 C, which is 7.450 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.780 C, and the margin is measured, not chosen: 2.780 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

19:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.000 C, which is 8.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.859 C, and the margin is measured, not chosen: 2.859 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

20:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.890 C, which is 9.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.907 C, and the margin is measured, not chosen: 2.907 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

21:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.000 C, which is 8.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.663 C, and the margin is measured, not chosen: 3.663 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.890 C, which is 9.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.937 C, and

the margin is measured, not chosen: 3.937 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.330 C, which is 9.670 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.914 C, and the margin is measured, not chosen: 3.914 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.