

AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location Amazon Web Services CMH53, OH -- station KCMH, America/New_York
Committed pair OSM 562775657 -> 1020374278
Amazon Web Services CMH50 / Amazon Web Services CMH56
Facade gap 147.2 m between the two halls
Weather record 43,786 real hourly records from KCMH
Plume physics 576 steady-state solves on this site's own footprints; worst intake rise 0.3516 C at 200 deg

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2024-02-28 (crossing)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 8 of 24 hours with 1 mode change. That is 3 more than the reactive incumbent, at 0 unsafe hours against its 2. 5 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 8 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 5 of 24 hours free cooling, 2 mode change(s), 2 unsafe hour(s)
5 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	no	dew point	15.786	18.0	16.281	4.055
01	mechanical	no	dew point	15.784	18.0	16.281	3.633
02	mechanical	no	dew point	16.366	18.0	16.841	3.693
03	mechanical	yes	switch budget	16.404	18.0	18.633	3.275
04	mechanical	yes	switch budget	16.366	18.0	19.217	2.920
05	mechanical	yes	switch budget	16.625	18.0	17.229	2.597
06	mechanical	yes	switch budget	17.117	18.0	15.001	2.676
07	mechanical	yes	switch budget	17.444	18.0	15.352	2.253

08	mechanical	no	dry-bulb	20.524	18.0	14.507	2.888
09	mechanical	no	dry-bulb	24.700	18.0	10.560	3.834
10	mechanical	no	dry-bulb	27.998	18.0	6.670	4.933
11	mechanical	no	dry-bulb	28.551	18.0	4.440	5.784
12	mechanical	no	dry-bulb	27.383	18.0	3.330	5.901
13	mechanical	no	dry-bulb	27.562	18.0	2.780	5.792
14	mechanical	no	dry-bulb	25.481	18.0	1.670	4.909
15	mechanical	no	dry-bulb	19.857	18.0	1.670	4.512
16	FREE	yes	-	12.964	18.0	0.560	3.276
17	FREE	yes	-	9.118	18.0	0.000	3.334
18	FREE	yes	-	5.734	18.0	-1.110	2.668
19	FREE	yes	-	4.092	18.0	-1.670	3.082
20	FREE	yes	-	1.828	18.0	-2.220	3.338
21	FREE	yes	-	1.270	18.0	-2.780	3.686
22	FREE	yes	-	0.213	18.0	-3.890	4.186
23	FREE	yes	-	-0.309	18.0	-3.889	4.278

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 15.786 C would have passed. The outside air is too HUMID: the dew-point bound is 15.56 C against a 15.0 C maximum, failing by 0.56 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

01:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 15.784 C would have passed. The outside air is too HUMID: the dew-point bound is 15.56 C against a 15.0 C maximum, failing by 0.56 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

02:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 16.366 C would have passed. The outside air is too HUMID: the dew-point bound is 15.56 C against a 15.0 C maximum, failing by 0.56 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

03:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.404 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.366 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.625 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one

later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.117 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.444 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.524 C against a 18.0 C limit, so it fails by 2.524 C. It would take a limit 2.524 C higher, or a bound 2.524 C tighter, to change this hour.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.700 C against a 18.0 C limit, so it fails by 6.700 C. It would take a limit 6.700 C higher, or a bound 6.700 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.998 C against a 18.0 C limit, so it fails by 9.998 C. It would take a limit 9.998 C higher, or a bound 9.998 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 28.551 C against a 18.0 C limit, so it fails by 10.551 C. It would take a limit 10.551 C higher, or a bound 10.551 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.383 C against a 18.0 C limit, so it fails by 9.383 C. It would take a limit 9.383 C higher, or a bound 9.383 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.562 C against a 18.0 C limit, so it fails by 9.562 C. It would take a limit 9.562 C higher, or a bound 9.562 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 25.481 C against a 18.0 C limit, so it fails by 7.481 C. It would take a limit 7.481 C higher, or a bound 7.481 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.857 C against a 18.0 C limit, so it fails by 1.857 C. It would take a limit 1.857 C higher, or a bound 1.857 C tighter, to change this hour.

16:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.964 C, which is 5.036 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.276 C, and the margin is measured, not chosen: 3.102 C of group-conditional forecast error for this hour of day, plus 0.1739 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

17:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.118 C, which is 8.882 C

under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.334 C, and the margin is measured, not chosen: 3.096 C of group-conditional forecast error for this hour of day, plus 0.2382 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

18:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 5.734 C, which is 12.266 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.668 C, and the margin is measured, not chosen: 2.494 C of group-conditional forecast error for this hour of day, plus 0.1742 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

19:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 4.092 C, which is 13.908 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.082 C, and the margin is measured, not chosen: 2.880 C of group-conditional forecast error for this hour of day, plus 0.2022 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

20:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 1.828 C, which is 16.172 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.339 C, and the margin is measured, not chosen: 3.181 C of group-conditional forecast error for this hour of day, plus 0.1579 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

21:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 1.269 C, which is 16.731 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.686 C, and the margin is measured, not chosen: 3.527 C of group-conditional forecast error for this hour of day, plus 0.1595 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 0.213 C, which is 17.787 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.186 C, and the margin is measured, not chosen: 3.973 C of group-conditional forecast error for this hour of day, plus 0.2132 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is -0.309 C, which is 18.309 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.278 C, and the margin is measured, not chosen: 4.027 C of group-conditional forecast error for this hour of day, plus 0.2508 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.