

AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location Novartis, TX -- station KFTW, America/Chicago
Building OSM 1227550179
Novartis
Facade gap not applicable -- one building, no second facade
Weather record 43,350 real hourly records from KFTW
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-01-06 (clear_cool)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor none
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 13 of 24 hours with 1 mode change. That is 4 more than the reactive incumbent, at 0 unsafe hours against its 0. 10 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 13 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 9 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
10 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	yes	switch budget	12.662	18.0	11.670	1.117
01	mechanical	yes	switch budget	12.937	18.0	12.220	1.012
02	mechanical	yes	switch budget	13.217	18.0	12.780	0.943
03	mechanical	yes	switch budget	13.492	18.0	13.330	0.893

04	mechanical	yes	switch budget	14.047	18.0	13.890	0.847
05	mechanical	yes	switch budget	14.047	18.0	13.330	0.777
06	mechanical	yes	switch budget	14.877	18.0	13.890	0.954
07	mechanical	yes	switch budget	14.882	18.0	12.780	0.829
08	mechanical	yes	switch budget	16.267	18.0	13.330	1.275
09	mechanical	yes	switch budget	17.382	18.0	12.220	1.657
10	mechanical	no	dry-bulb	18.492	18.0	13.330	2.144
11	FREE	yes	-	17.932	18.0	12.220	1.923
12	FREE	yes	-	17.382	18.0	13.890	1.395
13	FREE	yes	-	16.542	18.0	12.220	1.240
14	FREE	yes	-	14.882	18.0	11.110	1.085
15	FREE	yes	-	14.322	18.0	9.440	1.000
16	FREE	yes	-	12.657	18.0	8.890	0.998
17	FREE	yes	-	11.267	18.0	8.330	1.136
18	FREE	yes	-	9.877	18.0	8.330	1.185
19	FREE	yes	-	9.322	18.0	8.330	1.359
20	FREE	yes	-	8.767	18.0	8.330	1.199
21	FREE	yes	-	9.322	18.0	8.890	1.350
22	FREE	yes	-	9.327	18.0	8.890	1.119
23	FREE	yes	-	9.602	18.0	8.890	1.212

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin
actual = what the intake temperature turned out to be, from the station record
margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.662 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

01:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.937 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

02:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.217 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

03:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.492 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.047 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes

per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.047 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.877 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.882 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.267 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

09:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.382 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.492 C against a 18.0 C limit, so it fails by 0.492 C. It would take a limit 0.492 C higher, or a bound 0.492 C tighter, to change this hour.

11:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.932 C, which is 0.068 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.923 C, and the margin is measured, not chosen: 1.771 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

12:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.382 C, which is 0.618 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.395 C, and the margin is measured, not chosen: 1.243 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

13:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.542 C, which is 1.458 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.240 C, and the margin is measured, not chosen: 1.088 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

14:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.882 C, which is 3.118 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.085 C, and the margin is measured, not chosen: 0.933 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

15:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.322 C, which is 3.678 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.000 C, and the margin is measured, not chosen: 0.848 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

16:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.657 C, which is 5.343 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.998 C, and the margin is measured, not chosen: 0.846 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

17:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.267 C, which is 6.733 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.136 C, and the margin is measured, not chosen: 0.984 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

18:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.877 C, which is 8.123 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.185 C, and the margin is measured, not chosen: 1.033 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

19:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.322 C, which is 8.678 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.359 C, and the margin is measured, not chosen: 1.207 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

20:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.767 C, which is 9.233 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.199 C, and the margin is measured, not chosen: 1.047 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

21:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.322 C, which is 8.678 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.350 C, and the margin is measured, not chosen: 1.198 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.327 C, which is 8.673 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.119 C, and the margin is measured, not chosen: 0.967 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.602 C, which is 8.398 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.212 C, and the margin is measured, not chosen: 1.060 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.