

AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

THE SITE

Location TX facility TX_way_1498670679 -- station KTPL, America/Chicago
Building OSM 1498670679
OSM way 1498670679
Facade gap not applicable -- one building, no second facade
Weather record 43,374 real hourly records from KTPL
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-11-03 (clear_cool)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 8 of 24 hours with 1 mode change. That is 4 more than the reactive incumbent, at 0 unsafe hours against its 0. 4 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 8 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 4 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
4 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	no	dew point	12.780	18.0	13.890	4.464
01	mechanical	no	dew point	12.780	18.0	13.890	3.480
02	mechanical	no	dew point	13.330	18.0	13.330	3.219
03	mechanical	no	dew point	13.340	18.0	13.330	2.820

04	mechanical	yes	switch budget	13.890	18.0	12.220	3.036
05	mechanical	yes	switch budget	13.890	18.0	11.670	2.689
06	mechanical	yes	switch budget	14.440	18.0	11.110	2.888
07	mechanical	yes	switch budget	15.000	18.0	11.110	2.351
08	mechanical	no	dew point	17.220	18.0	10.000	2.586
09	mechanical	no	dry-bulb	21.110	18.0	10.000	3.909
10	mechanical	no	dry-bulb	23.880	18.0	9.440	5.563
11	mechanical	no	dry-bulb	25.560	18.0	9.440	6.057
12	mechanical	no	dry-bulb	26.670	18.0	9.440	6.407
13	mechanical	no	dry-bulb	26.670	18.0	9.440	6.216
14	mechanical	no	dry-bulb	22.230	18.0	9.440	4.480
15	mechanical	no	dry-bulb	18.890	18.0	9.440	3.161
16	FREE	yes	-	15.560	18.0	9.440	2.544
17	FREE	yes	-	13.330	18.0	9.440	2.693
18	FREE	yes	-	11.110	18.0	8.890	2.904
19	FREE	yes	-	8.890	18.0	8.890	2.949
20	FREE	yes	-	7.770	18.0	8.890	3.602
21	FREE	yes	-	7.220	18.0	8.890	3.993
22	FREE	yes	-	7.220	18.0	8.330	4.381
23	FREE	yes	-	7.770	18.0	8.330	4.646

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin
actual = what the intake temperature turned out to be, from the station record
margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 12.780 C would have passed. The outside air is too HUMID: the dew-point bound is 15.55 C against a 15.0 C maximum, failing by 0.55 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

01:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 12.780 C would have passed. The outside air is too HUMID: the dew-point bound is 15.56 C against a 15.0 C maximum, failing by 0.56 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

02:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 13.330 C would have passed. The outside air is too HUMID: the dew-point bound is 15.56 C against a 15.0 C maximum, failing by 0.56 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

03:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 13.340 C would have passed. The outside air is too HUMID: the dew-point bound is 15.01 C against a 15.0 C maximum, failing by 0.01 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.890 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.890 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot

give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.440 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 17.220 C would have passed. The outside air is too HUMID: the dew-point bound is 15.01 C against a 15.0 C maximum, failing by 0.01 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.110 C against a 18.0 C limit, so it fails by 3.110 C. It would take a limit 3.110 C higher, or a bound 3.110 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.880 C against a 18.0 C limit, so it fails by 5.880 C. It would take a limit 5.880 C higher, or a bound 5.880 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 25.560 C against a 18.0 C limit, so it fails by 7.560 C. It would take a limit 7.560 C higher, or a bound 7.560 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.670 C against a 18.0 C limit, so it fails by 8.670 C. It would take a limit 8.670 C higher, or a bound 8.670 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.670 C against a 18.0 C limit, so it fails by 8.670 C. It would take a limit 8.670 C higher, or a bound 8.670 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.230 C against a 18.0 C limit, so it fails by 4.230 C. It would take a limit 4.230 C higher, or a bound 4.230 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.890 C against a 18.0 C limit, so it fails by 0.890 C. It would take a limit 0.890 C higher, or a bound 0.890 C tighter, to change this hour.

16:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.560 C, which is 2.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.544 C, and the margin is measured, not chosen: 2.544 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this

lead time.

17:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.330 C, which is 4.670 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.693 C, and the margin is measured, not chosen: 2.693 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

18:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.110 C, which is 6.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.904 C, and the margin is measured, not chosen: 2.904 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

19:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.890 C, which is 9.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.949 C, and the margin is measured, not chosen: 2.949 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

20:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 7.770 C, which is 10.230 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.602 C, and the margin is measured, not chosen: 3.602 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

21:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 7.220 C, which is 10.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.993 C, and the margin is measured, not chosen: 3.993 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 7.220 C, which is 10.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.381 C, and the margin is measured, not chosen: 4.381 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 7.770 C, which is 10.230 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.646 C, and the margin is measured, not chosen: 4.646 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.