

## AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

### THE SITE

Location VA facility VA\_way\_1333205263 -- station KJY0, America/New\_York  
Committed pair OSM 1128589933 -> 1333205263  
OSM way 1128589933 / OSM way 1333205263  
Facade gap 189.4 m between the two halls  
Weather record 43,249 real hourly records from KJY0  
Plume physics 576 steady-state solves on this site's own footprints; worst intake rise 1.0172 C at 355 deg

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

### THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-03-25 (clear\_cool)  
Plant limit 18.0 C  
Notice required 6 h  
Forecast skill 0.00 relative to persistence  
Level anchor sensor  
Condenser bank longest facade  
Switch budget 2 mode changes per day  
Minimum dwell 3 h  
Max dew point 15.0 C (Green Grid WP#46 p.6)

### WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 10 of 23 hours with 2 mode changes. 7 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 10 of 23 hours free cooling, 2 mode change(s), 0 unsafe hour(s)  
Incumbent 10 of 23 hours free cooling, 2 mode change(s), 0 unsafe hour(s)  
7 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

### EVERY HOUR, AND THE REASON FOR IT

| hh | mode | safe | binding | bound  | limit | actual | margin |
|----|------|------|---------|--------|-------|--------|--------|
| 00 | FREE | yes  | -       | 8.235  | 18.0  | 9.000  | 3.993  |
| 01 | FREE | yes  | -       | 8.235  | 18.0  | 9.000  | 3.340  |
| 02 | FREE | yes  | -       | 9.235  | 18.0  | 9.000  | 3.688  |
| 03 | FREE | yes  | -       | 9.235  | 18.0  | 9.000  | 3.191  |
| 04 | FREE | yes  | -       | 9.235  | 18.0  | 10.000 | 2.855  |
| 05 | FREE | yes  | -       | 9.235  | 18.0  | 9.000  | 2.477  |
| 06 | FREE | yes  | -       | 9.091  | 18.0  | 10.000 | 1.915  |
| 07 | FREE | yes  | -       | 11.123 | 18.0  | 10.000 | 2.749  |
| 08 | FREE | yes  | -       | 13.088 | 18.0  | 10.000 | 2.730  |

|    |            |     |               |        |      |        |       |
|----|------------|-----|---------------|--------|------|--------|-------|
| 09 | FREE       | yes | -             | 16.087 | 18.0 | 10.000 | 3.788 |
| 10 | mechanical | no  | dry-bulb      | 20.080 | 18.0 | 10.000 | 5.092 |
| 11 | mechanical | no  | dry-bulb      | 21.073 | 18.0 | 11.000 | 5.685 |
| 12 | mechanical | no  | dry-bulb      | 23.073 | 18.0 | 11.000 | 5.731 |
| 13 | mechanical | no  | dry-bulb      | 23.077 | 18.0 | 11.000 | 5.806 |
| 14 | mechanical | no  | dry-bulb      | 21.235 | 18.0 | 12.000 | 5.100 |
| 15 | mechanical | no  | refusal       | 19.172 | 18.0 | 13.000 | 4.599 |
| 16 | mechanical | yes | switch budget | 16.105 | 18.0 | 14.000 | 3.268 |
| 17 | mechanical | yes | switch budget | 15.056 | 18.0 | 14.000 | 3.058 |
| 18 | mechanical | yes | switch budget | 13.049 | 18.0 | 14.000 | 2.841 |
| 19 | mechanical | yes | switch budget | 12.235 | 18.0 | 13.000 | 3.789 |
| 20 | mechanical | yes | switch budget | 11.082 | 18.0 | 13.000 | 3.085 |
| 21 | mechanical | yes | switch budget | 12.082 | 18.0 | 12.000 | 3.973 |
| 23 | mechanical | yes | switch budget | 13.073 | 18.0 | 13.000 | 4.271 |

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

## THE REASONING, HOUR BY HOUR

---

### 00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.235 C, which is 9.765 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.993 C, and the margin is measured, not chosen: 3.757 C of group-conditional forecast error for this hour of day, plus 0.2352 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

### 01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.235 C, which is 9.765 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.340 C, and the margin is measured, not chosen: 3.105 C of group-conditional forecast error for this hour of day, plus 0.2352 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

### 02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.235 C, which is 8.765 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.688 C, and the margin is measured, not chosen: 3.453 C of group-conditional forecast error for this hour of day, plus 0.2352 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

### 03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.235 C, which is 8.765 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.191 C, and the margin is measured, not chosen: 2.956 C of group-conditional forecast error for this hour of day, plus 0.2352 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

### 04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.235 C, which is 8.765 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.855 C, and the margin is measured, not chosen: 2.620 C of group-conditional forecast error for this hour of day, plus 0.2352 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

### 05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.235 C, which is 8.765 C

under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.477 C, and the margin is measured, not chosen: 2.241 C of group-conditional forecast error for this hour of day, plus 0.2352 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

**06:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 9.091 C, which is 8.909 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.915 C, and the margin is measured, not chosen: 1.824 C of group-conditional forecast error for this hour of day, plus 0.0912 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

**07:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 11.123 C, which is 6.877 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.749 C, and the margin is measured, not chosen: 2.626 C of group-conditional forecast error for this hour of day, plus 0.1230 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

**08:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 13.088 C, which is 4.912 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.730 C, and the margin is measured, not chosen: 2.642 C of group-conditional forecast error for this hour of day, plus 0.0877 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

**09:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 16.087 C, which is 1.913 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.788 C, and the margin is measured, not chosen: 3.702 C of group-conditional forecast error for this hour of day, plus 0.0868 C for how much the plume could move if the wind direction differs from the one planned for, at the measured spread of wind direction over this lead time.

**10:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 20.080 C against a 18.0 C limit, so it fails by 2.080 C. It would take a limit 2.080 C higher, or a bound 2.080 C tighter, to change this hour.

**11:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 21.073 C against a 18.0 C limit, so it fails by 3.073 C. It would take a limit 3.073 C higher, or a bound 3.073 C tighter, to change this hour.

**12:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 23.073 C against a 18.0 C limit, so it fails by 5.073 C. It would take a limit 5.073 C higher, or a bound 5.073 C tighter, to change this hour.

**13:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 23.077 C against a 18.0 C limit, so it fails by 5.077 C. It would take a limit 5.077 C higher, or a bound 5.077 C tighter, to change this hour.

**14:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 21.235 C against a 18.0 C limit, so it fails by 3.235 C. It would take a limit 3.235 C higher, or a bound 3.235 C tighter, to change this hour.

**15:00 MECHANICAL [refusal]**

Mechanical, and the reason is a REFUSAL rather than a temperature. At this wind bearing a building sits between the condensers and the air intake. The dispersion model has no

representation of a building standing in the flow, so any number it produced here would be meaningless. The agent declines to certify the hour instead of returning a figure it cannot stand behind.

**16:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.105 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**17:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.056 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**18:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.049 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**19:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.235 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**20:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 11.081 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**21:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.081 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**23:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.073 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.