

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location NTT Silicon Valley SV1 Data Center, CA -- station KSJC, America/Los_Angeles
Building OSM 888253616
Facade gap NTT Silicon Valley SV1 Data Center
Weather record not applicable -- one building, no second facade
Weather record 43,747 real hourly records from KSJC
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-10-22 (chatter)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 7 of 24 hours with 1 mode change. That is 4 more than the reactive incumbent, at 0 unsafe hours against its 2. 6 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 7 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 3 of 24 hours free cooling, 2 mode change(s), 2 unsafe hour(s)
6 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	yes	switch budget	17.220	18.0	17.220	0.762
01	mechanical	yes	switch budget	17.220	18.0	17.220	0.676
02	mechanical	yes	switch budget	17.775	18.0	18.330	0.577
03	mechanical	yes	switch budget	17.500	18.0	17.780	0.490
04	mechanical	no	dry-bulb	18.050	18.0	18.330	0.701
05	mechanical	no	dry-bulb	18.050	18.0	17.220	0.639
06	mechanical	yes	-	16.390	18.0	14.440	0.441

07	mechanical	yes	-	17.495	18.0	14.440	0.723
08	mechanical	no	dry-bulb	18.055	18.0	14.440	0.943
09	mechanical	no	dry-bulb	18.050	18.0	14.440	1.489
10	mechanical	no	dry-bulb	19.165	18.0	15.560	1.585
11	mechanical	no	dry-bulb	19.720	18.0	17.220	1.299
12	mechanical	no	dry-bulb	19.720	18.0	17.780	1.320
13	mechanical	no	dry-bulb	20.000	18.0	18.330	1.283
14	mechanical	no	dry-bulb	20.275	18.0	18.890	1.160
15	mechanical	no	dry-bulb	19.170	18.0	17.780	1.069
16	mechanical	no	dry-bulb	18.610	18.0	18.330	0.793
17	FREE	yes	-	17.500	18.0	16.670	0.955
18	FREE	yes	-	16.110	18.0	16.110	0.943
19	FREE	yes	-	15.835	18.0	15.000	1.163
20	FREE	yes	-	15.000	18.0	14.440	1.323
21	FREE	yes	-	14.995	18.0	14.440	1.262
22	FREE	yes	-	14.445	18.0	14.440	0.860
23	FREE	yes	-	14.165	18.0	14.440	0.608

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin
actual = what the intake temperature turned out to be, from the station record
margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

01:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

02:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.775 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

03:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.500 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

04:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.050 C against a 18.0 C limit, so it fails by 0.050 C. It would take a limit 0.050 C higher, or a bound 0.050 C tighter, to change this hour.

05:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.050 C against a 18.0 C limit, so it

fails by 0.050 C. It would take a limit 0.050 C higher, or a bound 0.050 C tighter, to change this hour.

06:00 MECHANICAL

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.390 C against a 18.0 C limit. The schedule is what forbids it: no relaxation of either the switch budget or the dwell would free it, so the surrounding hours are worth more. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.495 C against a 18.0 C limit. The schedule is what forbids it: no relaxation of either the switch budget or the dwell would free it, so the surrounding hours are worth more. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.055 C against a 18.0 C limit, so it fails by 0.055 C. It would take a limit 0.055 C higher, or a bound 0.055 C tighter, to change this hour.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.050 C against a 18.0 C limit, so it fails by 0.050 C. It would take a limit 0.050 C higher, or a bound 0.050 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.165 C against a 18.0 C limit, so it fails by 1.165 C. It would take a limit 1.165 C higher, or a bound 1.165 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.720 C against a 18.0 C limit, so it fails by 1.720 C. It would take a limit 1.720 C higher, or a bound 1.720 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.720 C against a 18.0 C limit, so it fails by 1.720 C. It would take a limit 1.720 C higher, or a bound 1.720 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.000 C against a 18.0 C limit, so it fails by 2.000 C. It would take a limit 2.000 C higher, or a bound 2.000 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.275 C against a 18.0 C limit, so it fails by 2.275 C. It would take a limit 2.275 C higher, or a bound 2.275 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.170 C against a 18.0 C limit, so it fails by 1.170 C. It would take a limit 1.170 C higher, or a bound 1.170 C tighter, to change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.610 C against a 18.0 C limit, so it fails by 0.610 C. It would take a limit 0.610 C higher, or a bound 0.610 C tighter, to change this hour.

17:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.500 C, which is 0.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.955 C, and the margin is measured, not chosen: 0.955 C of group-conditional forecast error for

this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

18:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.110 C, which is 1.890 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.943 C, and the margin is measured, not chosen: 0.943 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

19:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.835 C, which is 2.165 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.163 C, and the margin is measured, not chosen: 1.163 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

20:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.000 C, which is 3.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.323 C, and the margin is measured, not chosen: 1.323 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

21:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.995 C, which is 3.005 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.262 C, and the margin is measured, not chosen: 1.262 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.445 C, which is 3.555 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.860 C, and the margin is measured, not chosen: 0.860 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.165 C, which is 3.835 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.608 C, and the margin is measured, not chosen: 0.608 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.