

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location Google - Thornton, CO -- station KIBM, America/Denver
Building OSM 426586135
Google - Thornton
Facade gap not applicable -- one building, no second facade
Weather record 43,440 real hourly records from KIBM
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2025-04-11 (crossing)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 1 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 2 of 24 hours with 1 mode change. The reactive incumbent took 10 hours -- 8 more -- but declared 1 unsafe hour against the agent's 0. The incumbent had to break its own switch budget 1 time to stay safe; the agent never did. 10 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 2 of 24 hours free cooling, 1 mode change(s), 0 unsafe hour(s)
Incumbent 10 of 24 hours free cooling, 2 mode change(s), 1 unsafe hour(s)
the incumbent broke its own switch budget 1 time(s) to stay safe
10 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	mechanical	yes	switch budget	4.775	18.0	4.440	1.205
01	mechanical	yes	switch budget	4.355	18.0	3.330	1.217
02	mechanical	yes	switch budget	4.080	18.0	2.610	1.208
03	mechanical	yes	switch budget	3.110	18.0	0.560	1.206
04	mechanical	yes	switch budget	2.275	18.0	0.000	1.139
05	mechanical	yes	switch budget	1.610	18.0	-1.000	1.209

06	mechanical	yes	switch budget	1.360	18.0	-0.780	1.389
07	mechanical	yes	switch budget	6.390	18.0	5.780	2.219
08	mechanical	yes	switch budget	10.585	18.0	10.890	2.834
09	mechanical	yes	switch budget	15.720	18.0	18.610	3.083
10	mechanical	no	dry-bulb	20.695	18.0	23.220	2.677
11	mechanical	no	dry-bulb	22.555	18.0	25.000	1.927
12	mechanical	no	dry-bulb	25.585	18.0	25.890	1.459
13	mechanical	no	dry-bulb	27.110	18.0	26.000	1.215
14	mechanical	no	dry-bulb	27.695	18.0	26.500	1.215
15	mechanical	no	dry-bulb	27.885	18.0	27.110	1.353
16	mechanical	no	dry-bulb	27.580	18.0	27.610	1.616
17	mechanical	no	dry-bulb	27.000	18.0	27.110	1.774
18	mechanical	no	dry-bulb	24.750	18.0	23.110	1.849
19	mechanical	no	dry-bulb	22.750	18.0	18.890	2.050
20	mechanical	no	dry-bulb	20.750	18.0	15.000	2.207
21	mechanical	no	dry-bulb	18.165	18.0	13.330	1.977
22	FREE	yes	-	15.805	18.0	12.500	1.535
23	FREE	yes	-	15.140	18.0	14.720	1.341

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin
actual = what the intake temperature turned out to be, from the station record
margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 4.775 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

01:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 4.355 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

02:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 4.080 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

03:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 3.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

04:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 2.275 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is

also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

05:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 1.610 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

06:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 1.360 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

07:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 6.390 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

08:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.585 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

09:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.720 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 1 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.695 C against a 18.0 C limit, so it fails by 2.695 C. It would take a limit 2.695 C higher, or a bound 2.695 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.555 C against a 18.0 C limit, so it fails by 4.555 C. It would take a limit 4.555 C higher, or a bound 4.555 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 25.585 C against a 18.0 C limit, so it fails by 7.585 C. It would take a limit 7.585 C higher, or a bound 7.585 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.110 C against a 18.0 C limit, so it fails by 9.110 C. It would take a limit 9.110 C higher, or a bound 9.110 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.695 C against a 18.0 C limit, so it fails by 9.695 C. It would take a limit 9.695 C higher, or a bound 9.695 C tighter, to

change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.885 C against a 18.0 C limit, so it fails by 9.885 C. It would take a limit 9.885 C higher, or a bound 9.885 C tighter, to change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.580 C against a 18.0 C limit, so it fails by 9.580 C. It would take a limit 9.580 C higher, or a bound 9.580 C tighter, to change this hour.

17:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.000 C against a 18.0 C limit, so it fails by 9.000 C. It would take a limit 9.000 C higher, or a bound 9.000 C tighter, to change this hour.

18:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.750 C against a 18.0 C limit, so it fails by 6.750 C. It would take a limit 6.750 C higher, or a bound 6.750 C tighter, to change this hour.

19:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.750 C against a 18.0 C limit, so it fails by 4.750 C. It would take a limit 4.750 C higher, or a bound 4.750 C tighter, to change this hour.

20:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.750 C against a 18.0 C limit, so it fails by 2.750 C. It would take a limit 2.750 C higher, or a bound 2.750 C tighter, to change this hour.

21:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.165 C against a 18.0 C limit, so it fails by 0.165 C. It would take a limit 0.165 C higher, or a bound 0.165 C tighter, to change this hour.

22:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.805 C, which is 2.195 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.535 C, and the margin is measured, not chosen: 1.535 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

23:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.140 C, which is 2.860 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.341 C, and the margin is measured, not chosen: 1.341 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.