

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location IA facility IA_way_191655977 -- station KCBF, America/Chicago
Building OSM 191655977
OSM way 191655977
Facade gap not applicable -- one building, no second facade
Weather record 42,455 real hourly records from KCBF
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2022-04-12 (crossing)
Plant limit 21.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 13 of 24 hours with 2 mode changes. The reactive incumbent took 15 hours -- 2 more -- but declared 1 unsafe hour against the agent's 0. 2 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 13 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 15 of 24 hours free cooling, 2 mode change(s), 1 unsafe hour(s)
2 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	8.000	21.0	8.000	0.846
01	FREE	yes	-	8.000	21.0	8.000	0.764
02	FREE	yes	-	8.000	21.0	8.000	0.708
03	FREE	yes	-	9.000	21.0	10.000	0.646
04	FREE	yes	-	9.000	21.0	10.000	0.597
05	FREE	yes	-	9.500	21.0	10.000	1.042
06	FREE	yes	-	10.500	21.0	10.000	0.914
07	FREE	yes	-	11.500	21.0	11.000	1.019

08	FREE	yes	-	13.000	21.0	12.000	1.215
09	FREE	yes	-	14.000	21.0	11.000	1.843
10	FREE	yes	-	15.500	21.0	12.000	1.807
11	FREE	yes	-	16.500	21.0	13.000	1.790
12	FREE	yes	-	16.500	21.0	15.000	1.551
13	mechanical	no	dew point	19.000	21.0	20.000	1.427
14	mechanical	no	dry-bulb	23.000	21.0	28.000	1.337
15	mechanical	no	dry-bulb	24.500	21.0	31.000	0.796
16	mechanical	no	dry-bulb	27.000	21.0	32.000	0.835
17	mechanical	no	dry-bulb	30.000	21.0	31.000	0.905
18	mechanical	no	dry-bulb	30.500	21.0	30.000	0.944
19	mechanical	no	dry-bulb	29.500	21.0	27.000	1.339
20	mechanical	no	dry-bulb	22.500	21.0	14.000	1.534
21	mechanical	no	dry-bulb	22.000	21.0	14.000	1.473
22	mechanical	yes	switch budget	20.000	21.0	13.000	1.228
23	mechanical	yes	switch budget	12.500	21.0	11.000	0.980

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.000 C, which is 13.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.846 C, and the margin is measured, not chosen: 0.846 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.000 C, which is 13.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.764 C, and the margin is measured, not chosen: 0.764 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.000 C, which is 13.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.708 C, and the margin is measured, not chosen: 0.708 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.000 C, which is 12.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.646 C, and the margin is measured, not chosen: 0.646 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.000 C, which is 12.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.597 C, and the margin is measured, not chosen: 0.597 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 9.500 C, which is 11.500 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.042 C, and the margin is measured, not chosen: 1.042 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind

direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 10.500 C, which is 10.500 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 0.914 C, and the margin is measured, not chosen: 0.914 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.500 C, which is 9.500 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.019 C, and the margin is measured, not chosen: 1.019 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.000 C, which is 8.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.215 C, and the margin is measured, not chosen: 1.215 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

09:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.000 C, which is 7.000 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.843 C, and the margin is measured, not chosen: 1.843 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

10:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 15.500 C, which is 5.500 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.807 C, and the margin is measured, not chosen: 1.807 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

11:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.500 C, which is 4.500 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.790 C, and the margin is measured, not chosen: 1.790 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

12:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.500 C, which is 4.500 C under the 21.0 C plant limit. That bound is the forecast plus a margin of 1.551 C, and the margin is measured, not chosen: 1.551 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

13:00 MECHANICAL [dew point]

Mechanical, and TEMPERATURE IS NOT THE REASON -- the dry-bulb bound of 19.000 C would have passed. The outside air is too HUMID: the dew-point bound is 15.50 C against a 15.0 C maximum, failing by 0.50 C. Cool but damp air condenses on cold surfaces inside the hall, which is why real economizers gate on humidity and not on temperature alone.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.000 C against a 21.0 C limit, so it fails by 2.000 C. It would take a limit 2.000 C higher, or a bound 2.000 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 24.500 C against a 21.0 C limit, so it fails by 3.500 C. It would take a limit 3.500 C higher, or a bound 3.500 C tighter, to change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.000 C against a 21.0 C limit, so it fails by 6.000 C. It would take a limit 6.000 C higher, or a bound 6.000 C tighter, to change this hour.

17:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 30.000 C against a 21.0 C limit, so it fails by 9.000 C. It would take a limit 9.000 C higher, or a bound 9.000 C tighter, to change this hour.

18:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 30.500 C against a 21.0 C limit, so it fails by 9.500 C. It would take a limit 9.500 C higher, or a bound 9.500 C tighter, to change this hour.

19:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 29.500 C against a 21.0 C limit, so it fails by 8.500 C. It would take a limit 8.500 C higher, or a bound 8.500 C tighter, to change this hour.

20:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.500 C against a 21.0 C limit, so it fails by 1.500 C. It would take a limit 1.500 C higher, or a bound 1.500 C tighter, to change this hour.

21:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.000 C against a 21.0 C limit, so it fails by 1.000 C. It would take a limit 1.000 C higher, or a bound 1.000 C tighter, to change this hour.

22:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 20.000 C against a 21.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

23:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.500 C against a 21.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.