

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location EdgeConneX Detroit DET01, MI -- station KVLL, America/Detroit
Building OSM 377585075
EdgeConneX Detroit DET01
Facade gap not applicable -- one building, no second facade
Weather record 43,132 real hourly records from KVLL
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2024-04-29 (crossing)
Plant limit 18.0 C
Notice required 3 h
Forecast skill 0.50 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point gate off

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 9 of 23 hours with 2 mode changes. 4 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 9 of 23 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 9 of 23 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
4 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	13.000	18.0	13.000	0.844
01	FREE	yes	-	13.055	18.0	13.000	0.765
02	FREE	yes	-	13.610	18.0	14.000	0.702
03	FREE	yes	-	13.140	18.0	13.000	0.658
04	FREE	yes	-	13.195	18.0	13.000	0.662
05	FREE	yes	-	13.780	18.0	13.000	0.675
06	FREE	yes	-	13.415	18.0	13.000	0.728
07	FREE	yes	-	14.360	18.0	14.000	0.852
08	FREE	yes	-	17.305	18.0	18.000	1.221

09	mechanical	no	dry-bulb	20.500	18.0	22.000	1.706
10	mechanical	no	dry-bulb	22.530	18.0	24.000	1.776
11	mechanical	no	dry-bulb	25.000	18.0	25.000	1.690
13	mechanical	no	dry-bulb	26.470	18.0	26.000	1.248
14	mechanical	no	dry-bulb	27.000	18.0	26.000	1.103
15	mechanical	no	dry-bulb	27.500	18.0	27.000	0.951
16	mechanical	yes	-	14.055	18.0	0.000	0.869
17	mechanical	no	dry-bulb	23.610	18.0	20.000	0.804
18	mechanical	no	dry-bulb	23.835	18.0	20.000	0.891
19	mechanical	yes	-	9.000	18.0	18.000	0.865
20	mechanical	no	dry-bulb	19.000	18.0	18.000	1.119
21	mechanical	no	dry-bulb	19.000	18.0	18.000	1.179
22	mechanical	yes	switch budget	17.500	18.0	17.000	1.133
23	mechanical	yes	switch budget	17.500	18.0	17.000	0.985

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.000 C, which is 5.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.844 C, and the margin is measured, not chosen: 0.844 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.055 C, which is 4.945 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.765 C, and the margin is measured, not chosen: 0.765 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.610 C, which is 4.390 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.702 C, and the margin is measured, not chosen: 0.702 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.140 C, which is 4.860 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.658 C, and the margin is measured, not chosen: 0.658 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.195 C, which is 4.805 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.662 C, and the margin is measured, not chosen: 0.662 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.780 C, which is 4.220 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.675 C, and the margin is measured, not chosen: 0.675 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.415 C, which is 4.585 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.728 C, and the margin is measured, not chosen: 0.728 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.360 C, which is 3.640 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 0.852 C, and the margin is measured, not chosen: 0.852 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 17.305 C, which is 0.695 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 1.221 C, and the margin is measured, not chosen: 1.221 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.500 C against a 18.0 C limit, so it fails by 2.500 C. It would take a limit 2.500 C higher, or a bound 2.500 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 22.530 C against a 18.0 C limit, so it fails by 4.530 C. It would take a limit 4.530 C higher, or a bound 4.530 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 25.000 C against a 18.0 C limit, so it fails by 7.000 C. It would take a limit 7.000 C higher, or a bound 7.000 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 26.470 C against a 18.0 C limit, so it fails by 8.470 C. It would take a limit 8.470 C higher, or a bound 8.470 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.000 C against a 18.0 C limit, so it fails by 9.000 C. It would take a limit 9.000 C higher, or a bound 9.000 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 27.500 C against a 18.0 C limit, so it fails by 9.500 C. It would take a limit 9.500 C higher, or a bound 9.500 C tighter, to change this hour.

16:00 MECHANICAL

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.055 C against a 18.0 C limit. The schedule is what forbids it: no relaxation of either the switch budget or the dwell would free it, so the surrounding hours are worth more. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

17:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.610 C against a 18.0 C limit, so it fails by 5.610 C. It would take a limit 5.610 C higher, or a bound 5.610 C tighter, to change this hour.

18:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.835 C against a 18.0 C limit, so it fails by 5.835 C. It would take a limit 5.835 C higher, or a bound 5.835 C tighter, to change this hour.

19:00 MECHANICAL

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 9.000 C against a 18.0 C limit. The schedule is what forbids it: no relaxation of either the switch budget or the dwell would free it, so the surrounding hours are worth more. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

20:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.000 C against a 18.0 C limit, so it fails by 1.000 C. It would take a limit 1.000 C higher, or a bound 1.000 C tighter, to change this hour.

21:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 19.000 C against a 18.0 C limit, so it fails by 1.000 C. It would take a limit 1.000 C higher, or a bound 1.000 C tighter, to change this hour.

22:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.500 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

23:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.500 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.