

INTAKE-ARBITER -- FREE-COOLING DECISION REPORT

An agent that decides, hour by hour, whether outside air can cool a data centre.

THE SITE

Location OR facility OR_way_1510517629 -- station KRLD, America/Los_Angeles
Building OSM 1510517629
OSM way 1510517629
Facade gap not applicable -- one building, no second facade
Weather record 42,730 real hourly records from KRLD
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-02-02 (clear_cool)
Plant limit 18.0 C
Notice required 6 h
Forecast skill 0.00 relative to persistence
Level anchor sensor
Condenser bank longest facade
Switch budget 2 mode changes per day
Minimum dwell 3 h
Max dew point 15.0 C (Green Grid WP#46 p.6)

WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 9 of 24 hours with 2 mode changes. 7 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 9 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
Incumbent 9 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)
7 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

EVERY HOUR, AND THE REASON FOR IT

hh	mode	safe	binding	bound	limit	actual	margin
00	FREE	yes	-	11.780	18.0	12.220	6.181
01	FREE	yes	-	12.000	18.0	11.220	5.469
02	FREE	yes	-	12.220	18.0	9.780	4.669
03	FREE	yes	-	12.220	18.0	9.220	3.890
04	FREE	yes	-	12.380	18.0	8.500	3.533
05	FREE	yes	-	12.500	18.0	8.720	3.161
06	FREE	yes	-	13.170	18.0	8.610	2.570
07	FREE	yes	-	14.500	18.0	9.110	2.968
08	FREE	yes	-	16.220	18.0	9.720	3.689

09	mechanical	no	dry-bulb	18.890	18.0	10.220	4.761
10	mechanical	no	dry-bulb	20.780	18.0	10.560	5.409
11	mechanical	no	dry-bulb	23.000	18.0	11.000	5.814
12	mechanical	no	dry-bulb	23.500	18.0	13.500	5.904
13	mechanical	no	dry-bulb	23.170	18.0	14.000	5.550
14	mechanical	no	dry-bulb	21.830	18.0	11.000	4.955
15	mechanical	no	dry-bulb	20.110	18.0	11.500	4.355
16	mechanical	no	dry-bulb	18.280	18.0	10.000	4.130
17	mechanical	yes	switch budget	16.330	18.0	9.220	3.804
18	mechanical	yes	switch budget	16.280	18.0	8.220	3.535
19	mechanical	yes	switch budget	14.110	18.0	6.500	3.230
20	mechanical	yes	switch budget	9.720	18.0	6.220	3.937
21	mechanical	yes	switch budget	10.280	18.0	6.390	5.354
22	mechanical	yes	switch budget	9.000	18.0	6.000	6.115
23	mechanical	yes	switch budget	8.610	18.0	4.440	6.530

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin

actual = what the intake temperature turned out to be, from the station record

margin = group-conditional forecast error for that hour of day, plus plume spread

THE REASONING, HOUR BY HOUR

00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 11.780 C, which is 6.220 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 6.181 C, and the margin is measured, not chosen: 6.181 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.000 C, which is 6.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 5.469 C, and the margin is measured, not chosen: 5.469 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.220 C, which is 5.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.669 C, and the margin is measured, not chosen: 4.669 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.220 C, which is 5.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.890 C, and the margin is measured, not chosen: 3.890 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.380 C, which is 5.620 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.533 C, and the margin is measured, not chosen: 3.533 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 12.500 C, which is 5.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.161 C, and the margin is measured, not chosen: 3.161 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

06:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 13.170 C, which is 4.830 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.570 C, and the margin is measured, not chosen: 2.570 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

07:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 14.500 C, which is 3.500 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.968 C, and the margin is measured, not chosen: 2.968 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

08:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 16.220 C, which is 1.780 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.689 C, and the margin is measured, not chosen: 3.689 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

09:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.890 C against a 18.0 C limit, so it fails by 0.890 C. It would take a limit 0.890 C higher, or a bound 0.890 C tighter, to change this hour.

10:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.780 C against a 18.0 C limit, so it fails by 2.780 C. It would take a limit 2.780 C higher, or a bound 2.780 C tighter, to change this hour.

11:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.000 C against a 18.0 C limit, so it fails by 5.000 C. It would take a limit 5.000 C higher, or a bound 5.000 C tighter, to change this hour.

12:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.500 C against a 18.0 C limit, so it fails by 5.500 C. It would take a limit 5.500 C higher, or a bound 5.500 C tighter, to change this hour.

13:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 23.170 C against a 18.0 C limit, so it fails by 5.170 C. It would take a limit 5.170 C higher, or a bound 5.170 C tighter, to change this hour.

14:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 21.830 C against a 18.0 C limit, so it fails by 3.830 C. It would take a limit 3.830 C higher, or a bound 3.830 C tighter, to change this hour.

15:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 20.110 C against a 18.0 C limit, so it fails by 2.110 C. It would take a limit 2.110 C higher, or a bound 2.110 C tighter, to change this hour.

16:00 MECHANICAL [dry-bulb]

Mechanical. The upper bound on intake air is 18.280 C against a 18.0 C limit, so it fails by 0.280 C. It would take a limit 0.280 C higher, or a bound 0.280 C tighter, to change this hour.

17:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.330 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here

would cost a better one later.

18:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.280 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

19:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

20:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 9.720 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

21:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 10.280 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

22:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 9.000 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

23:00 MECHANICAL [switch budget]

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 8.610 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by INTAKE-ARBITER/src/report.py. Verified by being read back: the file was reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.