

## AGENTIC-ARBITER -- FREE-COOLING DECISION REPORT

Data centres over-cool, continuously, because nobody can promise them the hours ahead. A chiller plant needs hours of notice to change mode, and a thermometer only ever reports NOW -- so the mechanical chillers keep running through hours that outside air could have cooled for free. FortyGuard closes that gap with heat intelligence 2 m above the ground, the height a ground-mounted condenser actually breathes. This agent turns that forecast into an hour-by-hour schedule carrying a calibrated safety bound.

### THE SITE

Location Aligned DFW-02, TX -- station KTKI, America/Chicago  
Building OSM 483286527  
Facade gap Aligned DFW-01  
Facade gap not applicable -- one building, no second facade  
Weather record 43,718 real hourly records from KTKI  
Plume physics NOT MODELLED. No other tagged data centre lies inside the solver's validated range, so there is no neighbour intake for a plume to arrive at: the quantity does not exist here rather than being unmeasured. This is a statement about the model's domain, not a claim that recirculation here is zero. A building's own exhaust re-entering its own intake is not modelled at any site in this project.

FortyGuard data: weather and geometry are this site's own; the four measured FortyGuard level offsets and the N-26 coverage record are Ashburn's, because only Ashburn has forecast/outcome day pairs. Quote the hours for this site; quote the coverage for Ashburn.

### THIS REPORT IS A SNAPSHOT, NOT THE LIVE PAGE

The interface recomputes the decision for whatever configuration a reader selects. This file was generated at build time for the ONE configuration named below, chosen because it is the configuration in which this site's agent does the most while still changing mode at least once. If the numbers on screen differ from the numbers here, the configuration differs -- compare the two lists before concluding anything else.

Day 2021-02-26 (clear\_cool)  
Plant limit 18.0 C  
Notice required 6 h  
Forecast skill 0.00 relative to persistence  
Level anchor sensor  
Condenser bank longest facade  
Switch budget 2 mode changes per day  
Minimum dwell 3 h  
Max dew point 15.0 C (Green Grid WP#46 p.6)

### WHAT THE AGENT DID ON THIS DAY

The agent ran free cooling for 10 of 24 hours with 2 mode changes. 9 hours were safe but still ran chillers, because the schedule could not afford them.

Agent 10 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)  
Incumbent 10 of 24 hours free cooling, 2 mode change(s), 0 unsafe hour(s)  
9 hour(s) passed every gate and still ran chillers, because the schedule could not afford them

### EVERY HOUR, AND THE REASON FOR IT

| hh | mode | safe | binding | bound | limit | actual | margin |
|----|------|------|---------|-------|-------|--------|--------|
| 00 | FREE | yes  | -       | 7.780 | 18.0  | 8.890  | 4.244  |
| 01 | FREE | yes  | -       | 8.330 | 18.0  | 8.890  | 3.830  |
| 02 | FREE | yes  | -       | 8.340 | 18.0  | 8.330  | 3.015  |
| 03 | FREE | yes  | -       | 8.890 | 18.0  | 7.780  | 3.079  |

|    |            |     |               |        |      |        |       |
|----|------------|-----|---------------|--------|------|--------|-------|
| 04 | FREE       | yes | -             | 8.890  | 18.0 | 7.220  | 2.738 |
| 05 | FREE       | yes | -             | 8.890  | 18.0 | 7.220  | 2.475 |
| 06 | FREE       | yes | -             | 9.440  | 18.0 | 7.220  | 2.627 |
| 07 | FREE       | yes | -             | 10.000 | 18.0 | 7.220  | 2.080 |
| 08 | FREE       | yes | -             | 12.770 | 18.0 | 7.780  | 3.145 |
| 09 | FREE       | yes | -             | 15.560 | 18.0 | 8.890  | 4.179 |
| 10 | mechanical | no  | dry-bulb      | 18.330 | 18.0 | 10.000 | 5.583 |
| 11 | mechanical | no  | dry-bulb      | 20.000 | 18.0 | 11.110 | 5.704 |
| 12 | mechanical | no  | dry-bulb      | 21.670 | 18.0 | 12.220 | 6.206 |
| 13 | mechanical | no  | dry-bulb      | 21.660 | 18.0 | 13.330 | 6.125 |
| 14 | mechanical | no  | dry-bulb      | 18.900 | 18.0 | 13.890 | 4.155 |
| 15 | mechanical | yes | switch budget | 17.230 | 18.0 | 13.890 | 3.115 |
| 16 | mechanical | yes | switch budget | 16.110 | 18.0 | 13.890 | 2.665 |
| 17 | mechanical | yes | switch budget | 15.550 | 18.0 | 13.890 | 3.089 |
| 18 | mechanical | yes | switch budget | 14.440 | 18.0 | 13.330 | 3.058 |
| 19 | mechanical | yes | switch budget | 13.330 | 18.0 | 12.220 | 2.979 |
| 20 | mechanical | yes | switch budget | 12.780 | 18.0 | 12.220 | 3.595 |
| 21 | mechanical | yes | switch budget | 12.220 | 18.0 | 10.000 | 4.094 |
| 22 | mechanical | yes | switch budget | 12.220 | 18.0 | 10.000 | 4.566 |
| 23 | mechanical | yes | switch budget | 12.230 | 18.0 | 9.440  | 4.280 |

bound = the agent's 90 %-nominal upper bound on intake air, forecast plus margin  
actual = what the intake temperature turned out to be, from the station record  
margin = group-conditional forecast error for that hour of day, plus plume spread

## THE REASONING, HOUR BY HOUR

---

### 00:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 7.780 C, which is 10.220 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.244 C, and the margin is measured, not chosen: 4.244 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

### 01:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.330 C, which is 9.670 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.830 C, and the margin is measured, not chosen: 3.830 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

### 02:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.340 C, which is 9.660 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.015 C, and the margin is measured, not chosen: 3.015 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

### 03:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.890 C, which is 9.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.079 C, and the margin is measured, not chosen: 3.079 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

### 04:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.890 C, which is 9.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.738 C, and the margin is measured, not chosen: 2.738 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

### 05:00 FREE-COOLING

Free cooling. The 90 %-nominal upper bound on intake air is 8.890 C, which is 9.110 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.476 C, and the margin is measured, not chosen: 2.476 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

**06:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 9.440 C, which is 8.560 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.627 C, and the margin is measured, not chosen: 2.627 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

**07:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 10.000 C, which is 8.000 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 2.080 C, and the margin is measured, not chosen: 2.080 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

**08:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 12.770 C, which is 5.230 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 3.145 C, and the margin is measured, not chosen: 3.145 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

**09:00 FREE-COOLING**

Free cooling. The 90 %-nominal upper bound on intake air is 15.560 C, which is 2.440 C under the 18.0 C plant limit. That bound is the forecast plus a margin of 4.179 C, and the margin is measured, not chosen: 4.179 C of group-conditional forecast error for this hour of day, plus 0.0000 C for how much the plume could move if the wind direction is off by the amount FortyGuard's forecast is actually off by.

**10:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 18.330 C against a 18.0 C limit, so it fails by 0.330 C. It would take a limit 0.330 C higher, or a bound 0.330 C tighter, to change this hour.

**11:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 20.000 C against a 18.0 C limit, so it fails by 2.000 C. It would take a limit 2.000 C higher, or a bound 2.000 C tighter, to change this hour.

**12:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 21.670 C against a 18.0 C limit, so it fails by 3.670 C. It would take a limit 3.670 C higher, or a bound 3.670 C tighter, to change this hour.

**13:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 21.660 C against a 18.0 C limit, so it fails by 3.660 C. It would take a limit 3.660 C higher, or a bound 3.660 C tighter, to change this hour.

**14:00 MECHANICAL [dry-bulb]**

Mechanical. The upper bound on intake air is 18.900 C against a 18.0 C limit, so it fails by 0.900 C. It would take a limit 0.900 C higher, or a bound 0.900 C tighter, to change this hour.

**15:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 17.230 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**16:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 16.110 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**17:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 15.550 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**18:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 14.440 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**19:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 13.330 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**20:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.780 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**21:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**22:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.220 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

**23:00 MECHANICAL [switch budget]**

Mechanical EVEN THOUGH THIS HOUR IS SAFE. Every gate passes -- the bound is 12.230 C against a 18.0 C limit. The schedule is what forbids it: the switch budget of 2 changes per day is already committed elsewhere. This is the one explanation a thermostat cannot give, because a thermostat has no plan to be constrained by. It is also why the decision is a schedule and not a comparison: spending a mode change here would cost a better one later.

Generated by AGENTIC-ARBITER/src/report.py. Verified by being read back: the file was

reopened after writing and every hour of the schedule, the headline counts and this site's own name were confirmed present.